


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <u>SEDGWICK</u>	Fraction <u>SW 1/4 SW 1/4 SW 1/4</u>	Section number <u>22</u>	Township number <u>T 28 S</u>	Range number <u>R 2 W E/W</u>															
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>5410 ANNAPOLIS</u>			3. Owner of well: <u>BILL LEOFORD</u> R.R. or street: <u>5410 ANNAPOLIS</u> City, state, zip code: <u>WINNIE, KS.</u>																	
4. Locate with "X" in section below: 			6. Bore hole dia. <u>11</u> in. Completion date <u>9-7-77</u> Well depth <u>40</u> ft.																	
5. Type and color of material			7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																	
<table border="1"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr> <td><u>TOPSOIL</u></td> <td><u>1</u></td> <td><u>10</u></td> </tr> <tr> <td><u>FINE TO MED. GRAVEL</u></td> <td><u>10</u></td> <td><u>20</u></td> </tr> <tr> <td><u>MED. - COARSE</u></td> <td><u>20</u></td> <td><u>38</u></td> </tr> <tr> <td><u>CLAY -</u></td> <td><u>38</u></td> <td><u>40</u></td> </tr> </tbody> </table>				From	To	<u>TOPSOIL</u>	<u>1</u>	<u>10</u>	<u>FINE TO MED. GRAVEL</u>	<u>10</u>	<u>20</u>	<u>MED. - COARSE</u>	<u>20</u>	<u>38</u>	<u>CLAY -</u>	<u>38</u>	<u>40</u>	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
	From	To																		
<u>TOPSOIL</u>	<u>1</u>	<u>10</u>																		
<u>FINE TO MED. GRAVEL</u>	<u>10</u>	<u>20</u>																		
<u>MED. - COARSE</u>	<u>20</u>	<u>38</u>																		
<u>CLAY -</u>	<u>38</u>	<u>40</u>																		
			9. Casing: Material <u>Steel</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>15</u> lbs./ft. Dia. <u>5</u> in. to <u> </u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>.200</u>																	
			10. Screen: Manufacturer's name <u>J&L</u> Type <u>100</u> Dia. <u>5"</u> Slot/gauze <u>.065</u> Length <u>10'</u> Set between <u>36</u> ft. and <u>40</u> ft. Gravel pack? <u>YES</u> Size range of material <u>1/4" to 1/2"</u>																	
			11. Static water level: <u>22</u> ft. below land surface Date <u>9-7-77</u> mo./day/yr.																	
			12. Pumping level below land surfaces: <u>22</u> ft. after <u>12</u> hrs. pumping <u>15</u> g.p.m. ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>30</u> g.p.m.																	
			13. Water sample submitted: <u> </u> mo./day/yr. Yes ☒ No ☐ Date <u> </u>																	
			14. Well head completion: ☒ Pitless adapter <u> </u> inches above grade																	
			15. Well grouted? <u>YES</u> With: <u> </u> Neat cement <u> </u> Bentonite <u> </u> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.																	
			16. Nearest source of possible contamination: <u>LAWN WATER</u> ft. <u>50</u> Direction <u>W</u> Type <u>WELL</u> Well disinfected upon completion? ☒ Yes ☐ No																	
			17. Pump: <u>Not installed</u> Manufacturer's name <u>DEPSTER</u> Model number <u>DA-532</u> HP <u>3/4</u> Volts <u>230</u> Length of drop pipe <u>35</u> ft. capacity <u>15</u> g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																	
18. Elevation:			19. Remarks: <u>This well was free of sand</u>																	
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is to the best of my knowledge and belief. <u>21st Electric Co.</u> <u>129</u> Business name License No. Address <u>512 W. 21st</u> Signed <u>J. Krum</u> Date <u>9-20-77</u> Authorized representative																	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5