

CORRECTION(S) TO WATER WELL RECORD (WWC-5)
(to rectify lacking or incorrect information)

County: Ford

Location listed as:

Section-Township-Range: 28-285-21W

Fraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): SW NE NE

Location changed to:

33-285-21W

SW NE NE

Other changes: Initial statements: _____

Changed to: _____

Comments: _____

verification method: DWR Application No., information in WIMAS database,
and mapping tool on KGS website.

initials: DRL date: 8/10/2010

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: 029 FORD		SW 1/4 NE 1/4 NE 1/4	28	T 28 S	R 21 W

Distance and direction from nearest town or city street address of well if located within city?
APPROX. 2 1/4 NORTH, 1 EAST & 1/4 MILES SOUTH OF BUCKLIN

2 WATER WELL OWNER:		ESTES JR., MAYNARD L.	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :		2700 BRANDON LANE	Application Number: 7,964
City, State, ZIP code :		DODGE CITY, KS 67801-	

3 LOCATE WELL'S LOCATION WITH		4 DEPTH OF COMPLETED WELL	150	ELEVATION:	0
AN "X" IN SECTION BOX:		Depth(s) Groundwater Encountered	1.	0 ft.	2. 0 ft. 3. 0 ft.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
										WELL'S STATIC WATER LEVEL 95 ft. below land surface measured on mo/day/yr 08/22/95																																																																																									
										Pump test data: Well water was 115 ft. after 4 hours pumping 320 gpm																																																																																									
										Estimated Yield 320 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm																																																																																									
										Bore Hole Diameter 24 in. to 150 ft., and in. to 0 ft.																																																																																									
										WELL WATER TO BE USED AS: 02 IRRIGATION																																																																																									
										Was a chemical/bacteriological sample submitted to department? No ;																																																																																									
										If yes, mo/day/yr sample was submitted										Water well disinfected? Yes																																																																															

5 TYPE OF BLANK CASING USED: 01 STEEL		CASING JOINTS: WELDED	
Blank casing diameter	16 in. to 150 ft., Dia	in. to 0 ft., Dia	in. to 0 ft.
Casing height above land surface	12 in., weight	42 lbs/ft. Wall thickness or gauge No. .250	
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL			
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT			

SCREEN PERFORATED INTERVALS:	From 100 ft. to 140 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 150 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE	
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: 14 ABAND. WELL	
Direction from well? SOUTH	How many feet? 250

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	02 SILT			
4	40	04 SANDY CLAY			
40	67	01 CLAY 07 FINE SAND			
67	75	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
75	80	31 CALICHE 01 CLAY			
80	100	05 SAND 23 SANDSTONE 36 GYP ROCK			
100	120	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
120	140	05 SAND 11 GRAVEL 30 ROCK & CLAY			
140	160	05 SAND 11 GRAVEL 28 ROCK			
160	170	01 CLAY 31 CALICHE 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/19/95 and this record is true to the best of my knowledge and belief. Kansas	
Water Well Contractor's License No. 145	This Water Well Record was completed on (mo/day/yr) 08/23/95
under the business name of HENKLE DRILLING & SUPPLY	by (signature)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

12 WATER WELL OWNER: ESTES JR., WAYNARD L.

Board of Agriculture, Division of Water Resources

Application Number: 7,964

LITHOLOGIC LOG

by (signature)

1 (mo/day/yr) 08/23/95
Benny Richman