

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well:	County <b>Ford</b>	Township name <b>Valley</b>	Fraction <b>CNE 1/4</b>	Section number <b>9</b>	Town number <b>T 28 S</b>	Range number <b>R 21 W</b>
---------------------	-----------------------	--------------------------------	----------------------------	----------------------------	------------------------------	-------------------------------

Distance and direction from nearest town or city: <b>4 miles North</b>	3 Owner of well: <b>Austin Farms</b>
Street address of well location if in city: <b>3/4 Mi. E. Bucklin</b>	Address: <b>Bucklin, Kansas</b>

Locate with "X" in section below:

N

S

← 1 Mile →

Sketch map:

4 Well depth: 80 ft. Date of completion 3-9-75  
Well diameter 28 in.

5  Cable tool  Rotary  Driven  Dug  
 Hollow rod  Jetted  Bored  Reverse rotary

6 Use:  Domestic  Public supply  Industry  
 Irrigation  Air conditioning  Commercial  
 Test well  \_\_\_\_\_

7 Casing: Material steel Height: above XXX  
Threaded  Welded  Surface 12 in.  
Diam. \_\_\_\_\_ Weight 37 lbs./ft.  
16 in. to 80 ft. depth Drive shoe?  Yes  No  
\_\_\_\_ in. to \_\_\_\_ ft. depth

2	Type and color of material	From	To
	Top soil & sand	0	10
	Sand	10	54
	Sand & gravel (water bearing)	54	80
	Shale	80	--
	(use a second sheet if needed)		

8 Screen:  
Manufacturer W.A. Brown  
Type punch perfor Dia. 16"  
Slot/gauze 3/16 Length 20'  
Set between 60 ft. and 80 ft.  
Fittings:  
Gravel pack  Yes  No Size range of material 1x5/8"

9 Static water level:  
40 ft. below land surface Date 3-10-75

10 Pumping level below land surfaces:  
40 ft. after 2 hrs. pumping 750 g.p.m.  
\_\_\_\_ ft. after \_\_\_\_ hrs. pumping \_\_\_\_ g.p.m.  
Estimated maximum yield 750 g.p.m.

11 Water sample submitted:  
 Yes  No Date \_\_\_\_\_

12 Well head completion: 12"  
 Pitless adapter  Inches above grade

13 Well grouted?  Yes  No  
 Neat cement  Bentonite  Clay mix  
Depth: From 0 ft. to 10 ft.

14 Nearest source of possible contamination: none  
ft. \_\_\_\_\_ Direction \_\_\_\_\_ Type \_\_\_\_\_  
Well disinfected upon completion?  Yes  No

15 Pump:  Not installed  
Manufacturer's name Fairbanks Morse  
Model number 7000 HP 80 Volts \_\_\_\_\_  
Length of drop pipe 70 ft. capacity 600 g.m.p.  
Type:  
 Submersible  Turbine  
 Jet  Reciprocating  
 Centrifugal  Other

16 Remarks: elevation

Topography: **Flat**

Hill  
 Slope  
 Upland  
 Valley

17 Water well contractor's certification:  
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Brau Drilling Co. 217  
Business name License No. \_\_\_\_\_  
Address Bucklin, Kansas  
Signed Richard Brau Date 3-10-75  
Authorized representative