

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: FORD	NW 1/4 SE 1/4 NE 1/4	4	T 28 S	R 21 W

Distance and direction from nearest town or city street address of well if located within city?
 5 MILES NORTH, 1.5 MILES EAST OF BUCKLIN

2 WATER WELL OWNER: DEMUTH, MIKE
 RR#, St. Address, Box # : 12981 RIDGE ROAD
 City, State, ZIP code : FORD, KS 67842-
 Board of Agriculture, Division of Water Resources
 Application Number: |

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M	W			X
i				
l				
e				
		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 40 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 22 ft. below land surface measured on mo/day/yr 04/25/05
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 40 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: LIVESTOCK

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 20 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS:	From	20 ft. to	40 ft., From	0 ft. to	0 ft.
	From	0 ft. to	0 ft., From	0 ft. to	0 ft.
GRAVEL PACK INTERVALS:	From	20 ft. to	40 ft., From	0 ft. to	0 ft.
	From	0 ft. to	0 ft., From	0 ft. to	0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: OIL/GAS WELL
 Direction from well? NORTH How many feet? 6000

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	SILT AND SAND			
10	25	SAND AND GRAVEL			
25	38	TAN CLAY			
38	40	GRAY SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/25/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 06/22/05 under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayse