

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: FORD NE 1/4 SE 1/4 SE 1/4 19 T 28 S R 21 W

Distance and direction from nearest town or city street address of well if located within city?
2 MILES NORTH, 1 MILE WEST OF BUCKLIN

2 WATER WELL OWNER: ELLIS, GILBERT
RR#, St. Address, Box #: 12572 X ROAD Board of Agriculture, Division of Water Resources
City, State, ZIP code: KINGSDOWN, KS 67842- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	---	NW	---	NE	---
M	W	---	---	---	E
i	---	---	---	---	---
l	---	SW	---	SE	---
e	---	---	---	---	---

4 DEPTH OF COMPLETED WELL 170 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 98 ft. below land surface measured on mo/day/yr 12/02/10
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 170 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: LIVESTOCK

Was a chemical/bacteriological sample submitted to department? No;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 150 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 160
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 150 ft. to 170 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 25 ft. to 170 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout Intervals: From 3 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: SEPTIC TANK How many feet? 5000
Direction from well? EAST

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	73	TAN CLAY			
73	86	SAND AND GRAVEL			
86	124	TAN CLAY			
124	170	SAND AND GRAVEL			
170	171	GRAY SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/02/10 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 06/25/11
under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayse