

1 LOCATION OF WATER WELL: County: <u>Ford</u>		Fraction <u>Lot 1, Blk 74</u> NW 1/4 SE 1/4 SW 1/4		Section Number <u>5</u>	Township Number <u>T 28 S</u>	Range Number <u>R 22 E/W</u>
Distance and direction from nearest town or city street address of well if located within city? <u>In Ford, Kansas: Lot 1, Block 74</u>						
2 WATER WELL OWNER: <u>City of Ford</u> RR#, St. Address, Box # : <u>P.O.Box 108</u> City, State, ZIP Code : <u>Ford, Kansas 67842</u> Board of Agriculture, Division of Water Resources Application Number: <u>39559</u>						
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>125.6'</u> ft. ELEVATION:				
1 Mile		Depth(s) Groundwater Encountered 1. <u>92'</u> ft. 2. ft. 3. ft.				
		WELL'S STATIC WATER LEVEL <u>59'</u> ft. below land surface measured on mo/day/yr				
		Pump test data: Well water was <u>109'</u> ft. after hours pumping gpm				
		Est. Yield <u>63</u> gpm: Well water was ft. after hours pumping gpm				
Bore Hole Diameter <u>1 7/8</u> in. to <u>1 1/2</u> in. to in. to ft.		WELL WATER TO BE USED AS: ☒ Public water supply 8 Air conditioning 11 Injection well				
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)						
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well						
Was a chemical/bacteriological sample submitted to Department? Yes ☒ No If yes, mo/day/yr sample was submitted <u>07/19/91</u> Water Well Disinfected? Yes ☒ No						
5 TYPE OF BLANK CASING USED:						
☒ Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile		CASING JOINTS: Glued Clamped		
<u>2</u> PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below)		☒ Welded		
7 Fiberglass				Threaded		
Blank casing diameter .. <u>8-5/8</u> in. to ft., Dia in. to ft., Dia in. to ft.						
Casing height above land surface <u>36"</u> in., weight lbs./ft. Wall thickness or gauge No. <u>0.375</u>						
TYPE OF SCREEN OR PERFORATION MATERIAL:						
1 Steel ☒ Stainless steel		5 Fiberglass		7 PVC 10 Asbestos-cement		
2 Brass 4 Galvanized steel		6 Concrete tile		8 RMP (SR) 11 Other (specify)		
				9 ABS 12 None used (open hole)		
SCREEN OR PERFORATION OPENINGS ARE:						
1 Continuous slot 3 Mill slot		5 Gauzed wrapped		8 Saw cut 11 None (open hole)		
2 Louvered shutter 4 Key punched		☒ Wire wrapped		9 Drilled holes		
		7 Torch cut		10 Other (specify)		
SCREEN-PERFORATED INTERVALS: From <u>95'</u> ft. to <u>125'</u> ft. From ft. to ft.						
From ft. to ft. From ft. to ft.						
GRAVEL PACK INTERVALS: From <u>20</u> ft. to <u>125'</u> ft. From ft. to ft.						
From ft. to ft. From ft. to ft.						
6 GROUT MATERIAL: ☒ Neat cement 2 Cement grout 3 Bentonite 4 Other						
Grout Intervals: From <u>0</u> ft. to <u>20'</u> ft. From ft. to ft. From ft. to ft.						
What is the nearest source of possible contamination:						
1 Septic tank 4 Lateral lines		7 Pit privy		10 Livestock pens 14 Abandoned water well		
2 Sewer lines 5 Cess pool		8 Sewage lagoon		11 Fuel storage 15 Oil well/Gas well		
3 Watertight sewer lines 6 Seepage pit		9 Feedyard		12 Fertilizer storage ☒ Other (specify below)		
				13 Insecticide storage <u>City Sewer Line</u>		
Direction from well? <u>West of Well</u> How many feet? <u>150'</u>						
FROM		TO		LITHOLOGIC LOG		
FROM		TO		PLUGGING INTERVALS		
0		2		Top Soil		
2		19		Sandy Clay		
19		28		Tan Clay		
28		36		Tan Clay, Sand Streaks		
36		75		Coarse Sand Small Gravel Loose		
75		117		Coarse Sand, Marble Gravel Loose		
117		140		Yellow Clay		
		140		Total Depth		
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>10/30/92</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>514</u> This Water Well Record was completed on (mo/day/yr) <u>11/27/92</u> under the business name of <u>Miller Gearhead & Pump Repair, Inc.</u> by (signature) <u>Eugene Miller</u>						