

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

2824W 4N5E
T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

ADB

1 Location of well:	County Ford	Township name Enterprise	Range 4N5E NE SE of NE	Section number 4	Town number T-28-S	Range number R-24-W
---------------------	-----------------------	------------------------------------	--	----------------------------	------------------------------	-------------------------------

Distance and direction from nearest town or city:

6 mi south & 4 mi east-Dodge City

Street address of well location if in city:

3 Owner of well:

Kindsvater Farms


Address:

Dodge City, Kansas

Locate with "X" in section below:

N

Sketch map:



4 Well depth: **270** ft. Date of completion **10-10-75**
Well diameter **28"** in.

5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug
☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary

6 Use: ☐ Domestic ☐ Public supply ☐ Industry
☒ Irrigation ☐ Air conditioning ☐ Commercial
☐ Test well ☐

7 Casing: Material **Metal** Weight: above/below
Threaded ☐ Welded ☒ Surface **12** in.
Diam. **16** in. Weight **30.30** lbs./ft.
16 in. to **270** ft. depth Drive shoe? ☐ Yes ☒ No
in. to ft. depth

2 Type and color of material

From

To

Surface

0 3

Sandy brown clay & fine sand

3 115

Good med. sand and gravel

115 126

Yellow clay

126 130

Good med. sand and gravel

130 146

Brown sandy clay

146 157

Half med. sand

157 172

A-1 med. sand & fine loose gravel

172 214

Caliche clay

214 221

Good med. sand & fine loose gravel

221 237

Sandrock & clay

237 242

Half med. loose sand

242 255

A-1 sand & gravel

255 265

Yellow clay

265 274

Blue shale

274 285

8 Screen:

Manufacturer **WA Brown**

Type **Free-flo** Dia. **16**

Slot/gauze **1/8** Length **2"**

Set between **126** ft. and **270** ft.

Fittings:
Gravel pack ☐ Yes ☒ No Size range of material **CMA**

9 Static water level:

120 ft. below land surface Date **10-10-75**

10 Pumping level below land surfaces:

170 ft. after **2** hrs. pumping **1050** g.p.m.

175 ft. after **2** hrs. pumping **1250** g.p.m.

Estimated maximum yield **1450** g.p.m.

11 Water sample submitted:

☐ Yes ☒ No Date

12 Well head completion:

☐ Pitless adapter ☒ Inches above grade

13 Well grouted? ☒ Yes ☐ No

☒ Neat cement ☐ Bentonite ☐

Depth: From **0** ft. to **10** ft.

14 Nearest source of possible contamination: **NA**

ft. Direction Type

Well disinfected upon completion? ☐ Yes ☒ No

15 Pump:

☒ Not installed

Manufacturer's name

Model number HP Volts

Length of drop pipe ft. capacity g.m.p.

Type:

☐ Submersible

☐ Turbine

☐ Jet

☐ Reciprocating

☐ Centrifugal

☐ Other

16 Remarks: elevation

Topography:

☐ Hill
☐ Slope
☒ Upland
☐ Valley

TOPO 2558
265
2295

17 Water well contractor's certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Ace-Hi Int. Inc. **190**

Business name License No.

Address **Dodge City, Ks**

Signed **Carl G. Little** Date **10-24-75**

Authorized representative