

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: FORD NE 1/4 NE 1/4 SB 1/4 # 20 T 28 S R 24 EW

Distance and direction from nearest town or city street address of well if located within city?  
 FROM DODGE CITY- 56 & 283 JCT. 8 SOUTH, 3 EAST & 1/2 SOUTH

2 WATER WELL OWNER: ALLEN, LEON Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: 12160 114 ROAD Application Number:  
 City, State, ZIP code: DODGE CITY, KS 67801-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

NW	NE		
W	X	E	
SW	SE		

4 DEPTH OF COMPLETED WELL 276 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 90 ft. below land surface measured on mo/day/yr 02/16/05  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 9 in. to 276 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLURD  
 Blank casing diameter 5 in. to 276 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 232 ft. to 272 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 276 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: ABANDONED WELL  
 Direction from well? SOUTHWEST How many feet? 70

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY			
20	40	32 TAN CLAY 35 CALACHIB			
40	60	32 TAN CLAY 35 CALACHIB 10 FINE-MEDSAND			
60	80	10 FINE-MEDSAND 17 CLAY LAYERS			
80	100	37 FIN-COAR SAN			
100	140	37 FIN-COAR SAN 22MED-COAR SAND			
140	160	37 FIN-COAR SAN 22MED-COAR SAND 05 CLAY			
160	180	37 FIN-COAR SAN 06 SMALL GRAVEL			
180	200	37 FIN-COAR SAN 06 SMALL GRAVEL 17 CLAY LAYER			
200	240	17 CLAY LAYERS 37 FIN-COAR SAN 19 LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/17/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 03/16/05 under the business name of JOB'S WELL SERVICE, INC. by (signature) *James Curt*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:    Fraction    Section Number    Township Number    Range Number  
COUNTY: FORD    NE 1/4 NE 1/4 SE 1/4    17 20    T 28    S    R 24    8W

2 WATER WELL OWNER:    ALLEN, LEON  
RR#, St. Address, Box #: 12160 114 ROAD    Board of Agriculture, Division of Water Resources  
City, State, ZIP code : DODGE CITY, KS    67801-    Application Number:

FROM	TO	LITHOLOGIC LOG
240	260	32 TAN CLAY 37 FIN-COAR SAN 19 LAYERS
260	280	32 TAN CLAY 37 FIN-COAR SAN 19 LAYERS
280	300	32 TAN CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/17/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179    This Water Well Record was completed on (mo/day/yr) 03/16/05 under the business name of JOE'S WELL SERVICE, INC.    by (signature) *Quintin Cook*