

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Ford

Location listed as:

Section-Township-Range: _____

Fraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): _____

Location ~~changed to~~:

23-28S-25W

NE NW NW

Other changes: Initial statements: Gray County

Changed to: Ford County

Comments: _____

verification method: Written & legal descriptions, position on plat map,
and South Dodge & Ensign SE 1:24,000 topo. map.

initials: DRL date: 10/18/2004

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 035 GRAY	Fraction NE 1/4 NW 1/4 NW 1/4	Section Number 23	Township Number T 28 S	Range Number R 25 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM DODGE CITY; APPX 8 3/4 MILES SOUTH

2 WATER WELL OWNER: RR#, St. Address, Box # : PO BOX 880 City, State, ZIP code : DODGE CITY, KS 67801-0880	CITY OF DODGE CITY Board of Agriculture, Division of Water Resources Application Number: 23,132
--	---

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \					
1	---	NW	---	NE	---
M	W				E
i					
l					
e					
\ /		SW		SE	
	---		---		

4 DEPTH OF COMPLETED WELL 199ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 102 ft. below land surface measured on mo/day/yr 05/03/04
Pump testdata: Well water was 122 ft. after 8 hours pumping 1000 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 40 in. to 199 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 05 PUB. WTR SUP

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 18 in. to 199 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 71 lbs/ft. Wall thickness or gauge No. .375
TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 147 ft. to 194 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 100 ft. to 199 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT BENTONITE
Grout Intervals: From 1 ft. to 90 ft., From 90 ft. to 100 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	67	01 CLAY			
67	76	04 SANDY CLAY 05 SAND 01 CLAY			
76	81	05 SAND 11 GRAVEL 01 CLAY			
81	86	05 SAND 11 GRAVEL 01 CLAY			
86	100	01 CLAY			
100	150	05 SAND 11 GRAVEL 01 CLAY			
150	163	05 SAND 11 GRAVEL 01 CLAY			
163	167	05 SAND 01 CLAY			
167	175	05 SAND 13 FINE GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/21/04 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/24/04
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	NE 1/4 NW 1/4 NW 1/4	23	T 28 S	R 25 W

2 WATER WELL OWNER:	CITY OF DODGE CITY	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	PO BOX 880	Application Number: 23,132
City, State, ZIP code :	DODGE CITY, KS 67801-0880	

FROM	TO	LITHOLOGIC LOG
175	177	01 CLAY
177	188	05 SAND 13 FINE GRAVEL 01 CLAY
188	194	05 SAND 13 FINE GRAVEL 01 CLAY
194	213	01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/21/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/24/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) Bruce J. Rinkmeier