

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County:

Ford

Location listed as:

Section-Township-Range: 26-28-25EFraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): NW SW NW

Location changed to:

26-28-25WNW SW NW

Other changes: Initial statements: _____

Changed to: _____

Comments: E changed to Wverification method: county maps, location and address informationinitials: MSdate: 3-3-06

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD NW 1/4 SW 1/4 NW 1/4 26 T 28 S R 25 E

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY - 10 SOUTH ON HIGHWAY 283 - 1 WEST & 1/4 S.

2 WATER WELL OWNER: CITY OF DODGE CITY
 RR#, St. Address, Box #: PO BOX 880 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

	NW	NE
X		
	SW	SE

4 DEPTH OF COMPLETED WELL 265 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 153 ft. below land surface measured on mo/day/yr 06/21/05
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 5 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 6 1-4 in. to 265 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: MONITORING

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: OTHER CASING MAT CASING JOINTS: GLUED
 Blank casing diameter 2 in. to 265 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 40
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 190 ft. to 260 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 180 ft. to 265 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 0 ft. to 180 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: TEST WELL
 Direction from well? NORTH How many feet? 8

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY			
20	80	32 TAN CLAY			
80	100	32 TAN CLAY 26 RED CLAY 24 THINROCLAYER			
100	120	32 TAN CLAY 26 RED CLAY 10 FINE-MEDSAND			
120	140	17 CLAY LAYERS 37 FIN-COAR SAN			
140	160	37 FIN-COAR SAN 24 THINROCLAYER			
160	200	37 FIN-COAR SAN			
200	220	02 FINE SAND			
220	240	02 FINE SAND 17 CLAY LAYERS			
240	260	02 FINE SAND			

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 08/30/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 08/31/05 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Justin Crick*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: FORD	NW 1/4 SW 1/4 NW 1/4	26	T 28 S	R 25 E

2 WATER WELL OWNER: CITY OF DODGE CITY

RR#, St. Address, Box # : PO BOX 880

City, State, ZIP code : DODGE CITY, KS 67801-

Board of Agriculture, Division of Water Resources

Application Number:

FROM	TO	LITHOLOGIC LOG
260	290	10 FINE-MEDSAND 05 CLAY

3 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/30/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 08/31/05 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*