

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County <i>Ford</i>	Township name <i>Concord</i>	Fraction <i>SW 1/4 SE 1/4</i>	Section number <i>31</i>	Town number <i>28</i>	Range number <i>26</i>
---------------------	-----------------------	---------------------------------	----------------------------------	-----------------------------	--------------------------	---------------------------


Distance and direction from nearest town or city: *North of Fowler Ks*

Street address of well location if in city:

3 Owner of well: *Bill Waters*

Address: *Fowler Ks*

Locate with "X" in section below:



Sketch map:

SEED

sculpture tank

House

new well

old well house

4 Well depth: *108* ft. Date of completion *5-27-75*
Well diameter *5* in.

5 Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary

6 Use: Domestic Public supply Industry
 Irrigation Air conditioning Commercial
 Test well

7 Casing: Material *Steel* Height: above/below
Threaded Welded Surface _____ in.
Diam. _____ Weight _____ lbs./ft. _____
5 in. to *108* ft. depth Drive shoe? Yes No
_____ in. to _____ ft. depth!

2	Type and color of material	From	To
	<i>Black top soil</i>	<i>0</i>	<i>6</i>
	<i>Sandy Clay</i>	<i>6</i>	<i>52</i>
	<i>Dry sand</i>	<i>52</i>	<i>75</i>
	<i>Clay</i>	<i>75</i>	<i>90</i>
	<i>Coarse Gravel</i>	<i>90</i>	<i>108</i>

8 Screen:
Manufacturer *Sunflower Screen*
Type *320* Dia. *5*
Slot/gauze *1/16"* Length *20*
Set between *38* ft. and *108* ft. _____
Fittings:
Gravel pack Yes No Size range of material *1/16" - 1/4"*

9 Static water level:
80 ft. below land surface Date *5-27-75*

10 Pumping level below land surfaces:
82 ft. after *1/2* hrs. pumping *10* g.p.m.
_____ ft. after _____ hrs. pumping _____ g.p.m.
Estimated maximum yield *25* g.p.m.

11 Water sample submitted:
 Yes No Date _____

12 Well head completion:
 Pitless adapter *12* inches above grade

13 Well grouted? Yes No
 Neat cement Bentonite _____
Depth: From *3* ft. to *18* ft.

14 Nearest source of possible contamination:
ft. *350* Direction *NE* Type *Hydro Tank*
Well disinfected upon completion? Yes No

15 Pump: Not installed
Manufacturer's name *F&W*
Model number *10BA15* HP *1HP* Volts *230*
Length of drop pipe *90* ft. capacity *19* g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

16 Remarks: elevation

Topography:
 Hill
 Slope
 Upland
 Valley

(use a second sheet if needed)

17 Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Burt Drg *101A*
Business name _____ License No. _____
Address *Frederick Ks*
Signed *M.R. Burtel* Date *6-25-75*
Authorized representative