

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

WELL NO-1

1 Location of well:	County GRAY	Township name EAST HESS	Fraction NE 1/4	Section number 1	Town number 28	Range number 27
Distance and direction from nearest town or city: SOUTH SIDE OF FORD-ENSIGN ROAD 3/4 MI. EAST OF MAINE STREET OF ENSIGN KAN			3 Owner of well: JOE KONECNY Address: 1700-8 AV. DODGE CITY KAN			
Locate with "X" in section below: N W E S 1 Mile			Sketch map:			4 Well depth: 206 ft. Date of completion _____ Well diameter 28 in.
						5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
						6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well
						7 Casing: Material STEEL Height: above/below Threaded ☐ Welded ☒ Surface 12 in. Diam. _____ Weight _____ lbs./ft. _____ 16 in. to 206 ft. depth Drive shoe? ☐ Yes ☐ No _____ in. to _____ ft. depth
2 Type and color of material			From	To	8 Screen: Manufacturer WABROWN Type BRIDGE Dia. 16 in Slot/gauze 8 Length _____ Set between 16 ft. and 206 ft. _____ Fittings: Gravel pack ☒ Yes ☐ No Size range of material 1/2 DOWN	
SURFACE			0	2	9 Static water level: 150 ft. below land surface Date _____	
CLAY			2	54	10 Pumping level below land surfaces: 190 ft. after 1 hrs. pumping 1400 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 1400 g.p.m.	
CLAY & CALICHE SAND LAYERS			54	60	11 Water sample submitted: ☐ Yes ☒ No Date _____	
CLAY & CALICHE			60	139	12 Well head completion: ☐ Pitless adapter ☒ 12 inches above grade	
CALICHE			139	142	13 Well grouted? ☒ Yes ☐ No ☐ Neat cement ☐ Bentonite ☒ CEMENT Depth: From _____ ft. to 10 ft.	
SAND & GRAVEL			142	200	14 Nearest source of possible contamination: ENSIGN ft. 800 Direction N Type DISPOSAL Well disinfected upon completion? ☐ Yes ☒ No	
HARD LAYER YELLOW CLAY			200	202	15 Pump: ☐ Not installed Manufacturer's name HYDRO Model number _____ HP _____ Volts _____ Length of drop pipe 202 ft. capacity 1400 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
SHALE			202	205	17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. JO JOHNSON DRILLING 183 Business name License No. Address DODGE CITY KAN Signed JO JOHNSON Date 10-31 Authorized representative	
16 Remarks: elevation Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley (use a second sheet if needed)						

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5