

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

3-1-77
Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Gray	Fraction NE $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$	Section number 27	Township number T 28 S	Range number R 28 E/W
2. Distance and direction from nearest town or city: Street address of well location if in city	4 south of Cimarron, Ks., 3 west, 1 3/4 south, 1/4 west, to Pivot Point, 20' south		3. Owner of well: R.R. or street: City, state, zip code:	Art Scroggins Cimarron, Ks. 67835	
4. Locate with "X" in section below:	Sketch map: 		6. Bore hole dia. 26 in. Completion date 8-1-75 Well depth 291 ft.		
5. Type and color of material	From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
			8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
			9. Casing: Material <input type="checkbox"/> Steel <input type="checkbox"/> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface Height: Above or <input type="checkbox"/> below RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 36.87 lbs./ft. Dia. 16 in. to 292 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219 MHC		
			10. Screen: Manufacturer's name <input type="checkbox"/> Johnson Division Type <input type="checkbox"/> Galv. Dia. 16" Slot/ <input type="checkbox"/> Length 20' Set between 260 ft. and 280 ft. Perf: 100-260 ft. and 280-291 ft. Gravel pack? <input checked="" type="checkbox"/> Yes Size range of material 1/2" down		
			11. Static water level: mo./day/yr. 61 ft. below land surface Date 8-12-75		
			12. Pumping level below land surfaces: 103 ft. after 2 hrs. pumping 528 g.p.m. 130 ft. after 4 hrs. pumping 1110 g.p.m. Estimated maximum yield 1100 g.p.m.		
			13. Water sample submitted: mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date		
			14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade		
			15. Well grouted? <input checked="" type="checkbox"/> Yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.		
			16. Nearest source of possible contamination: N/A ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
			17. Pump: Not installed Manufacturer's name <input type="checkbox"/> Peerless - FMC Model number 5199 HP 100 Volts Length of drop pipe 220 ft. capacity 1100 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)			18. Elevation: 19. Remarks: Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		
			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter-Wilson Drilling Co. 208 Business name <input type="checkbox"/> Box 493 Garden City, Ks. Address <input type="checkbox"/> License No. Signature <input type="checkbox"/> Date 11-20 Authorized representative		

McINTYRE WILKIN DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 737-3247 P.O. Box 493 GARDEN CITY, KANSAS 67846

Art Scroggins
Duane Ratzlaff (tenant)
Gray County
7-22-75

Location: $\frac{1}{4}$ miles south of Cimarron, 3 miles west, 1 3/4 south
 $\frac{1}{2}$ mile west to pivot point, 20 ft. south
Sect 27-28-8

Test #1

0	3	Top soil
3	26	Brown sandy clay
26	35	Fine sand
35	71	Brown sandy clay
71	100	Fine to med. sand & gravel (loose)
100	115	Fine to med. sand & gravel with coarse gravel
115	123	Brown sandy clay
123	126	Fine to med. sand & gravel (loose)
126	138	Brown & white sandy clay
138	151	Brown & white sandy clay mixed with white rock
151	171	Fine to med. sand & gravel (loose)
171	227	Brown sandy clay
227	291	Fine to med. sand & gravel (loose)
291	295	Yellow & gray clay
295	300	Shale

Static Water Level: 70