

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL: County: <u>Gray</u>		Fraction <u>NW 1/4 SE 1/4 NE 1/4</u>	Section Number <u>25</u>	Township Number <u>T 28 S</u>	Range Number <u>R 29 E/W</u>									
Distance and direction from nearest town or city street address of well if located within city? <u>From Montezuma, Jct. 13 Rd. and Geranium 1/2 mile south, 1/4 mile west.</u>			Global Positioning Systems (decimal degrees, min. of 4 digits) Latitude: _____ Longitude: _____ Elevation: _____ Datum: _____ Data Collection Method: _____											
2 WATER WELL OWNER: <u>Aaron Jantz</u> RR#, St. Address, Box # : <u>26503 11 Rd.</u> City, State, ZIP Code : <u>Montezuma, KS. 67867</u>														
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N <table border="1" style="width:100px; height:100px; text-align: center; margin: 10px auto;"><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td>X</td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr></table> S						X					4 DEPTH OF COMPLETED WELL <u>460</u> ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... <u>231</u> ft. below land surface measured on mo/day/yr. <u>5/6/09</u> Pump test data: Well water was..... ft. after..... hours pumping..... gpm Est. Yield..... gpm: Well water was..... ft. after..... hours pumping..... gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well ① Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u>; If yes, mo/day/yr Sample was submitted..... Water well disinfected? Yes <u>X</u> No			
	X													
5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) ① PVC 4 ABS 7 Fiberglass Blank casing diameter <u>5</u> in. to <u>320</u> ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface..... <u>12</u> in., Weight lbs./ft. Wall thickness or gauge No. <u>SDR 21</u> TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass ① PVC 9 ABS 11 Other (Specify) 2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped ⑧ Saw cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From..... <u>320</u> ft. to <u>460</u> ft., From ft. to ft. From..... ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From..... <u>24</u> ft. to <u>310</u> ft., From <u>320</u> ft. to <u>460</u> ft. From..... ft. to ft., From ft. to ft.														
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ③ Bentonite 4 Other Grout Intervals: From <u>4</u> ft. to <u>24</u> ft., From <u>310</u> ft. to <u>320</u> ft., From ft. to ft. What is the nearest source of possible contamination: ① Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide storage 16 Other (specify below) 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 15 Oil well/gas well Direction from well? <u>North</u> How many feet? <u>104</u>														
FROM		TO		LITHOLOGIC LOG										
0		2		Topsoil										
2		80		Tan clay & med. sand										
80		90		white rock										
90		97		Tan sandy										
97		105		Coarse sand										
105		146		Med. sand & white rock layers										
146		150		ochre & limestone										
150		140		Shale										
140		265		Sandstone										
265		270		Shale										
FROM		TO		PLUGGING INTERVALS										
270		280		Sandstone										
280		320		Shale										
320		360		Shale & Sandstone layers										
360		385		Sandstone										
385		415		Shale										
415		426		Sandstone										
426		431		Shale										
431		470		Sandstone										
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>5/6/09</u> ... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>533</u> ... This Water Well Record was completed on (mo/day/year) <u>10/2/09</u> ... under the business name of <u>Jantzen Water Well</u> by (signature) <u>[Signature]</u>														
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .														