

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Sedgwick	FRACTION SW 1/4 NW 1/4 SW 1/4	SECTION NUMBER 23	TOWNSHIP NUMBER T 28 S	RANGE NUMBER R 3W E/W
---	--	------------------------------------	---	--

Distance and direction from nearest town or city street address of well if located within city?
5116 S. 247th St. West Goddard, Kansas

2 WATER WELL OWNER: NAGEL, Curtis RR#,ST. ADDRESS,BOX #: 5116 S. 247th St. West CITY, STATE: Goddard, Kansas	ZIP CODE: _____ Application Number: _____ Board of Agriculture, Division of Water Resource
--	---

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: **120** ft. **ELEVATION:** _____ ft.
 Depth of groundwater Encountered: _____ ft.
WELL'S STATIC WATER LEVEL **30** FT. BELOW LAND SURFACE MEASURED ON **6/24/04**
 Pump test data: Well water was _____ ft. after _____ hours of pumping @ _____ gpm
 Est. Yield: _____ gpm Well water was _____ ft. after _____ hours of pumping @ _____ gpm
 Bore Hole Diameter **12** in. to **120** ft. and _____ in. to _____ ft.
WELL WATER TO BE USED AS:
☒ 1. Domestic ☐ 3. Feedlot ☐ 5. Public water supply ☐ 7. Lawn and garden only ☐ 9. Dewatering ☐ 11. Injection well
☐ 2. Irrigation ☐ 4. Industrial ☐ 6. Oil field water supply ☐ 8. Air conditioning ☐ 10. Monitoring well ☐ 12. Other (Specify below)
 Was a chemical/bacteriological sample submitted to Department? **YES** ☒ **NO** ; If yes, what mo/day/yr was sample submitted
 Was Water Well Disinfected? ☒ **YES** ☐ **NO**

5 TYPE OF CASING USED:
☒ 1. Steel ☐ 3. RPM (SR) ☐ 5. Wrought Iron ☐ 7. Fiberglass ☐ 9. Other (Specify below)
☒ 2. PVC ☐ 4. ABS ☐ 6. Asbestos-Cement ☐ 8. Concrete tile **SDR-26**
 Blank casing diameter **5** in. to **30** ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft.
 Casing height above land surface: **24** in., Weight: **2.35** lbs. / ft. Wall thickness or gauge No. **.214**
TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ 1. Steel ☐ 3. Stainless Steel ☐ 5. Fiberglass ☒ 7. PVC ☐ 9. ABS ☐ 11. Other (specify)
☐ 2. Brass ☐ 4. Galvanized ☐ 6. Concrete Tile ☐ 8. RMP (SR) ☐ 10. Asbestos-Cement ☐ 12. None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:
☐ 1. Continuous slot ☐ 3. Mill slot ☐ 5. Gauzed wrapped ☐ 7. Torch cut ☐ 9. Drilled holes ☐ 11. None (open hole)
☐ 2. Louvered shutter ☐ 4. Key punched ☐ 6. Wire wrapped ☒ 8. Saw cut ☐ 10. Other (specify)
SCREEN - PERFORATION INTERVAL From **30** ft. to **120** ft., From _____ ft. to _____ ft.
GRAVEL PACK INTERVALS: From **24** ft. to **120** ft., From _____ ft. to _____ ft.

CASING JOINTS: ☒ **Glued** ☐ Threaded
☐ Welded ☐ Clamped

6 GROUT MATERIALS: ☐ 1. Neat cement ☐ 2. Cement Grout ☐ 3. Bentonite Other **bentonite hole plug**
 Grout Intervals: From **4** ft. to **24** ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.
 What is the nearest source of possible contamination:
☐ 1. Septic tank ☐ 4. Lateral lines ☐ 7. Pit privy ☐ 10. Livestock pens ☐ 13. Insecticide storage ☐ 15. Oil well/Gas well
☐ 2. Sewer lines ☐ 5. Cess Pool ☐ 8. Sewage lagoon ☐ 11. Fuel storage ☐ 14. Abandon water well ☐ 16. Other (specify below)
☐ 3. Watertight sewer line ☐ 6. Seepage pit ☐ 9. Feed yard ☐ 12. Fertilizer storage **Non-Exsistent**
 Direction from well? _____ How many feet? _____

From	To	LITHOLOGIC LOG	From	To	LITHOLOGIC LOG
0	3	topsoil			
3	8	clay			
8	45	gray shale			
45	55	brown shale			
55	95	gray shale			
95	100	red shale			
100	118	gray shale-gypsum			
118	120	limestone			

7 Contractor's or Landowner's Certification: This water well was 1. ☒ **constructed** 2. **reconstructed** or 3. **plugged** under my jurisdiction and was completed on (mo/day/year) **6/24/2004** and this record is true to the best of my knowledge and belief.
 Kansas Water Well Contractor's License No. **236** This water well record was completed on (mo/day/year) **6/28/2004**
 under the business name of **Harp Well & Pump Service Inc.** by (signature) *J o d d S. H a r p*

J o d d S. H a r p