


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NE 1/4 SE 1/4	Section number 12	Township number T 28 S R 3W E/W	Range number
2. Distance and direction from nearest town or city: Street address of well location if in city: 3634 South 215th West Goddard, Kansas				3. Owner of well: Scott Gowen R.R. or street: 1146 Wood Avenue City, state, zip code: Wichita, Kansas		
4. Locate with "X" in section below: 				Sketch map:		
5. Type and color of material				Fram	To	6. Bore hole dia. 11 in. Completion date 12-21-78 Well depth 125 ft.
Topsoil				0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Sandy Clay				2	16	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Fine to Medium Coarse Sand				16	30	9. Casing: Material Styrene Height: Above or below 6 ft. Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight 12 lbs./ft. Dia. 5 in. to 125 ft. depth Wall Thickness: inches or Dia. 5 in. to 125 ft. depth gage No. 200
Blue Shale				30	125	10. Screen: Manufacturer's name Sunflower plastic Type styrene Dia. 5" Slot 1/16 Length 95' Set between 30 ft. and 125 ft. ft. and 125 ft. Gravel pack? yes Size range of material 1/4-1/8"
						11. Static water level: 17 ft. below land surface Date 12-21-78 mo./day/yr.
						12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.
						13. Water sample submitted: Yes No Date
						14. Well head completion: ☒ Pitless adapter 12 inches above grade
						15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.
						16. Nearest source of possible contamination: ft. 65 Direction East Type Septic Well disinfected upon completion? ☒ Yes tank No
						17. Pump: Not installed Manufacturer's name Jacuzzi Model number 7S4C HP 3/4 Volts 230 Length of drop pipe 100 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)						
18. Elevation:		19. Remarks: Flat ground		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas 67209 Signed M. Arnold Date 1-12-79 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5