


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 SW 1/4 NE 1/4	Section number 23	Township number T 28 S	Range number R 3W E/W
2. Distance and direction from nearest town or city: #23 Beaver Creek Ct Street address of well location if in city:				3. Owner of well: A.J. Schlegal Constr. R.R. or street: 130 Rhodes City, state, zip code: Wichita, Kansas 67233		
4. Locate with "X" in section below: N  Sketch map: Lake Waltanna Goddard, Kansas				6. Bore hole dia. 11 in. Completion date Well depth 120 ft. 5-3-77		
5. Type and color of material				From	To	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Topsoil				0	3	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Brown Clay				3	8	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 120 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gauge No. 200
Fine Sand				8	18	10. Screen Manufacturer's name Subflow Plastic
Red Shale				18	21	Type Styrene Dia. 5" Slot gauge 0.06 Length 95' Set between 25 ft. and 120 ft. ft. and ☐ ft. Gravel pack ☒ yes Size range of material 1/4-1/8"
Blue Shale				21	120	11. Static water level: 20 ft. below land surface Date 5-3-77 mo./day/yr.
						12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.
						13. Water sample submitted: mo./day/yr. Yes ☐ No ☐ Date
						14. Well head completion: ☒ Pitless adapter 12 inches above grade
						15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.
						16. Nearest source of possible contamination: ft. 75 Direction East Type City Sewer Line Well disinfected upon completion? ☒ Yes ☐ No
						17. Pump: ☐ Not installed Manufacturer's name Sta-rite Model number 20P4D02 HP 3/4 Volts 230 Length of drop pipe 110 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. Address Signed M. Arnold Date 6-30-77 Authorized representative		
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5