

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Sedgwick</u> Fraction <u>NW 1/4 SE 1/4 SE 1/4</u> Section number <u>23</u> Township number <u>T 28 S</u> Range number <u>R 3 E</u>			
2. Distance and direction from nearest town or city: <u>2 W. 4 3/4 So. boddard Ks</u> Street address of well location if in city: <u>#4 Lakewood Ct. Lake Waltanna</u>		3. Owner of well: <u>B. S. Enterprize</u> R.R. or street: <u>Cheney Ks 67025</u> City, state, zip code: <u>Cheney Ks 67025</u>	
4. Locate with "X" in section below: N W E S 1 Mile		6. Bore hole dia. <u>1 1/2</u> in. Completion date <u>6/7/78</u> Well depth <u>76</u> ft.	
5. Type and color of material		7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
From To		8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Top soil. 0 2 gray. red clay. 2 8 fine sand. 8 21 gray clay. 21 23 med. sand 23 31 Red shale 31 65 brown blue shale. 65 70 blue green shale. 70 72 Red shale. 72 76.		9. Casing: Material <u>Styrene</u> Height <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☒ PVC ☐ Weight <u>1.50</u> lbs./ft. Dia. <u>5</u> in. to <u>76</u> ft. depth Wall Thickness: inches or Dia. <u>5</u> in. to <u>76</u> ft. depth Gauge No. <u>200</u>	
Lake 1000ft N. W — also		10. Screen: Manufacturer's name <u>Sunflow</u> Type <u>200</u> Dia. <u>5 1/2</u> in. Slot/auze <u>1/16</u> Length <u>40</u> ft. Set between <u>36</u> ft. and <u>76</u> ft. Gravel pack? <u>yes</u> Size range of material <u>3/8</u>	
(Use a second sheet if needed)		11. Static water level: <u>28</u> ft. below land surface Date <u>6/7/78</u>	
		12. Pumping level below land surfaces: <u>55</u> ft. after <u>12</u> hrs. pumping <u>12</u> g.p.m. <u>55</u> ft. after <u>12</u> hrs. pumping <u>12</u> g.p.m. Estimated maximum yield <u>20-30</u> g.p.m.	
		13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>6/7/78</u>	
		14. Well head completion: <u>12</u> Pitless adapter <u>12</u> inches above grade	
		15. Well grouted? <u>yes</u> With: <u>Neat cement</u> ☐ Bentonite ☒ Concrete ☐ Depth: From <u>3</u> ft. to <u>13</u> ft.	
		16. Nearest source of water contamination: ft. <u>75</u> Direction <u>SE</u> Type <u>Septic</u> Well disinfected upon completion? ☒ Yes ☐ No	
		17. Pump: ☒ Not installed Manufacturer's name <u>HP</u> Model number <u>318</u> HP <u>3/8</u> Volts <u>115</u> Length of drop pipe <u>13</u> ft. capacity <u>3/8</u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:		19. Remarks: <u>Customer to furnish 4'x4'x4'</u> <u>slab around casing at grade</u> <u>Per State Regulations</u> <u>Signed X John C. Wright</u>	
Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Whitney Kelly</u> 318 Business name <u>Cheney</u> License No. <u>1/4 NW 1/4 SE 1/4</u> Address <u>Cheney</u> Signed <u>John C. Wright</u> Date <u>6/7/78</u> Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5