


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Sedgewick</u>		<u>NW 1/4 NW 1/4 SW 1/4</u>	<u>24</u>	<u>T 28 S</u>	<u>R 3 E</u>
Distance and direction from nearest town or city street address of well if located within city? <u>2 1/2 West 4 1/2 South Goddard, Kansas</u>					
2 WATER WELL OWNER: <u>Stan Dye</u>					
RR#, St. Address, Box # <u>P.O. Box 427</u>					
City, State, ZIP Code <u>Goddard, Ks 67052</u>					
Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL <u>80</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered <u>15</u> ft. 2. <u>15</u> ft. 3. <u>15</u> ft.			
		WELL'S STATIC WATER LEVEL <u>15</u> ft. below land surface measured on mo/day/yr <u>5-26-84</u>			
		Pump test data: Well water was <u>25</u> ft. after <u>1/2</u> hours pumping <u>20</u> gpm			
		Est. Yield <u>20-25</u> gpm: Well water was <u>80</u> ft. after <u>1/2</u> hours pumping <u>20</u> gpm			
		Bore Hole Diameter <u>11</u> in. to <u>80</u> ft. and <u>80</u> in. to <u>80</u> ft.			
		WELL WATER TO BE USED AS: ☒ Domestic ☐ 3 Feedlot ☐ 6 Oil field water supply ☐ 9 Dewatering ☐ 12 Other (Specify below)			
		☐ 2 Irrigation ☐ 4 Industrial ☐ 7 Lawn and garden only ☐ 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes <u>X</u> No <u>X</u> ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes <u>X</u> No <u>X</u>			
5 TYPE OF BLANK CASING USED:					
1 Steel ☒ RMP (SR) ☐ 5 Wrought iron ☐ 8 Concrete tile ☐ CASING JOINTS: Glued <u>X</u> Clamped <u>X</u>					
2 PVC ☐ 4 ABS ☐ 6 Asbestos-Cement ☐ 9 Other (specify below) ☐ Welded <u>X</u>					
3 Fiberglass ☐ ☐ Threaded <u>X</u>					
Blank casing diameter <u>5</u> in. to <u>20</u> ft. Dia <u>12</u> in. to <u>1.59</u> lbs./ft. Wall thickness or gauge No. <u>502-26</u>					
Casing height above land surface <u>12</u> in. weight <u>1.59</u> lbs./ft.					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel ☐ 3 Stainless steel ☐ 5 Fiberglass ☒ RMP (SR) ☐ 7 PVC ☐ 10 Asbestos-cement ☐ 11 Other (specify) ☐ 12 None used (open hole)					
2 Brass ☐ 4 Galvanized steel ☐ 6 Concrete tile ☐ 9 ABS ☐ 8 Saw cut ☐ 11 None (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot ☒ 3 Mill slot ☐ 6 Wire wrapped ☐ 9 Drilled holes ☐ 10 Other (specify) ☐					
2 Louvered shutter ☐ 4 Key punched ☐ 7 Torch cut ☐ 10 Other (specify) ☐					
SCREEN-PERFORATED INTERVALS: From <u>20</u> ft. to <u>80</u> ft. From <u>20</u> ft. to <u>80</u> ft. From <u>20</u> ft. to <u>80</u> ft.					
GRAVEL PACK INTERVALS: From <u>13</u> ft. to <u>80</u> ft. From <u>13</u> ft. to <u>80</u> ft. From <u>13</u> ft. to <u>80</u> ft.					
6 GROUT MATERIAL: 1 Neat cement ☐ 2 Cement grout ☒ 3 Bentonite ☐ 4 Other ☐					
Grout Intervals: From <u>3</u> ft. to <u>13</u> ft. From <u>3</u> ft. to <u>13</u> ft. From <u>3</u> ft. to <u>13</u> ft.					
What is the nearest source of possible contamination:					
☒ Septic tank ☐ 4 Lateral lines ☐ 7 Pit privy ☐ 10 Livestock pens ☐ 14 Abandoned water well					
☐ 2 Sewer lines ☐ 5 Cess pool ☐ 8 Sewage lagoon ☐ 11 Fuel storage ☐ 15 Oil well/Gas well					
☐ 3 Watertight sewer lines ☐ 6 Seepage pit ☐ 9 Feedyard ☐ 12 Fertilizer storage ☐ 16 Other (specify below)					
Direction from well? <u>North</u> How many feet? <u>80</u>					
FROM		TO		LITHOLOGIC LOG	
0		4		Top Soil	
4		24		Sand	
24		80		Gray Shale	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed ☐ (2) reconstructed or ☐ (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>5-26-84</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>318</u> This Water Well Record was completed on (mo/day/yr) <u>6-26-84</u> under the business name of <u>Weninger Drilling, Inc.</u> by (signature) <u>Weninger</u>					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					