

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 SE 1/4 NE 1/4	1	T 28 S	R 30 W	

Distance and direction from nearest town or city street address of well if located within city?
FROM MONTEZUMA ON BLACKTOP 4 NORTH & 5 WEST

2 WATER WELL OWNER:		LOVE, CARL	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #:	City, State, ZIP code	MONTEZUMA, KS 67867-	Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 346	ELEVATION: 0						
<table border="1"> <tr> <td>1</td> <td>NW</td> <td>SE</td> </tr> <tr> <td>2</td> <td>SW</td> <td>NE</td> </tr> </table>		1	NW	SE	2	SW	NE	Depth: Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.	WELL'S STATIC WATER LEVEL 252 ft. below land surface measured on 07/23/96 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 60 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
1	NW	SE							
2	SW	NE							
		Bore Hole Diameter 10 in. to 346 ft. and in. to 0 ft.	WELL WATER TO BE USED AS: DOMESTIC						
		Was a chemical/bacteriological sample submitted to department? No; If yes, no/day/yr sample was submitted. *water well disinfected? Yes							

5 TYPE OF BLANK CASING USED: PVC		CASING JOINTS: GLOUED	
Blank casing diameter 5 in. to 346 ft. Dia	in. to 0 ft. Dia	in. to 0 ft. Dia	in. to 0 ft. Dia
Casing height above land surface 12 in.	weight 200 lbs/ft.	Wall thickness or gauge No. 21	
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC			
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT			

SCREEN PERFORATED INTERVALS:	From 300 ft. to 340 ft.	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 0 ft. to 0 ft.	From 0 ft. to 0 ft.
	From 30 ft. to 346 ft.	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.	From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE		
Grout intervals: From 0 ft. to 30 ft.	From 0 ft. to 0 ft.	From 0 ft. to 0 ft.
What is the nearest source of possible contamination: ABANDONED WELL		How many feet? 25
Direction from well? NORTHEAST		

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL PINE SAND			
20	40	FINE SAND			
40	60	FINE SAND CALACHIE			
60	80	FINE - MED SAND			
80	100	FINE SAND COARSE SAND			
100	120	CLAY			
120	140	CLAY FINE SAND			
140	160	FINE SAND COARSE SAND SMALL GRAVEL			
160	180	FINE SAND CLAY LAYERS			
180	200	CLAY CALACHIE IN LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 07/25/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 08/12/96 under the business name of JOE'S WELL SERVICE, INC. *Signature: Judith Cribb*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 SE 1/4 NE 1/4	1	T 28 S	R 30 W	

2 WATER WELL OWNER:		LOVE, CARL	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #:	City, State, ZIP code	MONTEZUMA, KS 67867-	Application Number:

FROM	TO	LITHOLOGIC LOG
200	220	FINE SAND
220	240	FINE SAND CLAY
240	260	CLAY CALACHIE
260	280	FINE - MED SAND
280	300	FINE - MED SAND CLAY LAYERS
300	335	MED-COARSE SAND SMALL GRAVEL
335	350	CLAY FINE SAND