

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	SW 1/4 NW 1/4 SW 1/4	08	T 28 S	R 30 W

Distance and direction from nearest town or city street address of well if located within city?
FROM MONTEZUMA, APPX 10 MILES WEST & 1 1/2 MILE NORTH

2 WATER WELL OWNER:	ROBERT JOSSEYARD	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	333 CENTRE	Application Number: 14688
City, State, ZIP code :	HEREFORD, TX 79045-	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 468 ELEVATION: 0
	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

1 / \	WELL'S STATIC WATER LEVEL 233 ft. below land surface measured on mo/day/yr 04/25/07
	Pump test data: Well water was 263 ft. after 4 hours pumping 842 gpm

1	NW NE	Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
---	-------	---

M		Bore Hole Diameter 24 in. to 468 ft., and in. to 0 ft.
---	--	--

i	W E	WELL WATER TO BE USED AS: 02 IRRIGATION
---	-----	---

e	X SW SE	Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted
---	---------	---

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL	CASING JOINTS: WELDED
---------------------------------------	-----------------------

Blank casing diameter 16 in. to 468 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
--

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 251 ft. to 321 ft., From 426 ft. to 436 ft.
	From 376 ft. to 396 ft., From 453 ft. to 463 ft.

GRAVEL PACK INTERVALS:	From 20 ft. to 468 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE	
-------------------------------	--

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
---	--

What is the nearest source of possible contamination: 14 ABAND. WELL	
--	--

Direction from well? NORTHWEST	How many feet? 254
--------------------------------	--------------------

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	26	04 SANDY CLAY 07 FINE SAND			
26	68	05 SAND			
68	115	04 SANDY CLAY 05 SAND 20 LIMESTONE			
115	126	07 FINE SAND 08 MEDIUM SAND			
126	154	04 SANDY CLAY 05 SAND 20 LIMESTONE			
154	171	05 SAND			
171	173	04 SANDY CLAY			
173	189	05 SAND			
189	194	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/20/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145	This Water Well Record was completed on (mo/day/yr) 08/27/07
under the business name of HENKLE DRILLING & SUPPLY	by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	SW 1/4 NW 1/4 SW 1/4	08	T 28 S	R 30 W

2 WATER WELL OWNER: ROBERT JOSSEWARD

RR#, St. Address, Box #: 333 CENTRE

Board of Agriculture, Division of Water Resources

City, State, ZIP code : HEREFORD, TX 79045-

Application Number: 14688

FROM	TO	LITHOLOGIC LOG
194	199	05 SAND
199	203	04 SANDY CLAY
203	214	05 SAND
214	219	04 SANDY CLAY
219	250	05 SAND
250	264	05 SAND 13 FINE GRAVEL
264	276	05 SAND 01 CLAY
276	281	05 SAND 13 FINE GRAVEL
281	295	04 SANDY CLAY 05 SAND
295	310	05 SAND
310	321	05 SAND 01 CLAY
321	376	04 SANDY CLAY 07 FINE SAND
376	397	07 FINE SAND 08 MEDIUM SAND
397	425	SOAPSTONE 23 SANDSTONE
425	437	23 SANDSTONE
437	458	31 CALICHE 23 SANDSTONE
458	463	23 SANDSTONE
463	480	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/20/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/27/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

