


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Gray	Fraction NW 1/4 NW 1/4 SW 1/4	Section number 12	Township number T 28	Range number S R 30	E/W	
2. Distance and direction from nearest town or city:	3N, 6E of Montezuma, KS Street address or well location if in city:		3. Owner of well: Eugene Schmidt R.R. or street: R.R. City, state, zip code: Montezuma, KS				
4. Locate with "X" in section below:	Sketch map: 		5. Type and color of material				
			From	To			
Top soil		0	6	Type W/W Dia. 16"			
Tan clay		6	38	Slot/gauze 1/8" Length 40			
Fine sand		38	46	Set between 368 ft. and 408 ft.			
Tan clay, sand streaks		46	104	ft. and _____ ft.			
Fine to coarse sand, medium gravel		104	124	Gravel pack? XX Size range of material 4.7mm			
Fine to coarse sand		124	160	11. Static water level: 121 ft. below land surface Date 2/24/77			
Tan clay		160	168	12. Pumping level below land surfaces: 158 ft. after 2 hrs. pumping 2104 g.p.m.			
Fine to coarse sand, medium gravel		168	188	168 ft. after 1 hrs. pumping 2534 g.p.m.			
Tan Tan clay		188	208	Estimated maximum yield 3100 g.p.m.			
Fine to coarse sand		208	244	13. Water sample submitted: Yes X No Date _____			
Tan sandy clay		244	258	14. Well head completion: Pitless adapter X Inches above grade			
Tan clay (sticky)		258	314	15. Well grouted? X			
Fine sand, clay streaks		314	366	With: Neat cement X Bentonite Concrete			
Coarse sand, large gravel (loose)		366	408	Depth: From 0 ft. to 10 ft.			
Black shale		408	420	16. Nearest source of possible contamination: Unk.			
(Use a second sheet if needed)				ft. _____ Direction _____ Type _____			
18. Elevation:	19. Remarks:				Well disinfected upon completion? X Yes No		
Topography:					17. Pump: Not installed		
<input type="checkbox"/> Hill					Manufacturer's name U. S.		
<input type="checkbox"/> Slope					Model number _____ HP _____ Volts _____		
<input checked="" type="checkbox"/> Upland					Length of drop pipe 200 ft. capacity 1600 g.p.m.		
<input type="checkbox"/> Valley					Type: <input type="checkbox"/> Submersible X Turbine <input type="checkbox"/> Jet Reciprocating <input type="checkbox"/> Centrifugal Other		
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.							
Business name Layne-Western Co. License No. 102							
Address Garden City, KS							
Signed John L. Layne Date 26 May 77 Authorized representative John L. Layne							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5