


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Gray	Fraction <i>NW</i> NE 1/4 NE 1/4 NE 1/4	Section number 13	Township number T 28	Range number S R 30 E <i>W</i>	
2. Distance and direction from nearest town or city: 1 mile N and 5.5 miles W of Montezuma, Kansas	3. Owner of well: Mr. & Mrs. Henry Koehn Jr. R.R. or street: R R City, state, zip code: Montezuma, Kansas					
4. Locate with "X" in section below: 	Sketch map: 1000' W of NE corner of the NE 1/4, Sec. 13, of T28S, R30W, Gray County, Kansas					
5. Type and color of material	From	To	6. Bore hole dia. 28 in. Completion date 4-16-76 Well depth 220 ft.			
Top soil	0	2	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary			
Tan clay	2	31	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
Tan clay & fine sand	31	40	9. Casing: Material <i>STL</i> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft. Dia. 16 in. to 155 ft. depth, Wall thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219			
Tan clay	40	67	10. Screen: Manufacturer's name <i>Doerr, Cook</i> and Foster Louver WW and type <i>Milislot</i> Dia. 16" Slot/gauze 1/8" Length 65' Set between 155 ft. and 220 ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> yes Size range of material 3.1-7.5 mm			
Tan clay with sand & gravel	67	82	11. Static water level: mo./day/yr. 130 ft. below land surface Date 2-4-76			
Tan clay with limestone	82	102	12. Pumping level below land surfaces: 180 ft. after 1 hrs. pumping 1893 g.p.m. 185 ft. after 1 hrs. pumping 1697 g.p.m. Estimated maximum yield 2000 g.p.m.			
Fine to coarse sand with tan clay streaks	102	120	13. Water sample submitted: mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date			
Fine to coarse sand	120	137	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade			
Tan clay	137	147	15. Well grouted? <input checked="" type="checkbox"/> yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.			
Fine to coarse sand	147	164	16. Nearest source of possible contamination: Unk ft. Direction Type Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
Tan & white clay	164	182	17. Pump: Not installed Manufacturer's name <i>Layne & Bowler</i> Model number <i>12TL</i> HP 100 Volts Length of drop pipe 200 ft. capacity 1400 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
Fine to coarse sand med. gravel	182	220				
Tan & white clay with lite gravel streaks	220	300				
(Use a second sheet if needed)						
18. Elevation:	19. Remarks:					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne - Western Co. 150 Business name <i>Garden City, Kansas</i> License No. Address <i>Garden City, Kansas</i> Signed <i>R. L. Layne</i> Date <i>5-24-76</i> Authorized representative