

WATER WELL RECORD

Form WWC-5

1139404

Division of Water Resources App. No.

Well ID

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed, reconstructed, or plugged under my jurisdiction and was completed on (mo-day-year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. This Water Well Record was completed on (mo-day-year) under the business name of

Send one copy to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

Send one copy to KDHKS/WATER WELL UNIT and retain one for your records. Fee of \$30.00 for each united well. KS Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-3565. Visit us at <http://www.kdheks.gov/waterwell/index.html> KSA 82a-1212

Form	WWC5
Contractor	Hydro Resources Mid Continent, Inc.
Well Owner	Ron Jantz
Doc ID	1139404

Lithology

From	To	Lithologic Log
0	1	TOP SOIL
1	15	FINE SAND, SILT
15	25	SILT, FINE SAND & CLAY
25	45	LIGHT BROWN CLAY
45	93	BROWN CLAY W/ SAND STREAKS
93	120	GREEN & BROWN CLAY
120	155	LOOSE MEDIUM FINE TO MED SAND
155	189	LOOSE MEDIUM SAND W/ SOME COARSE SAND STREAKS
189	202	WHITE & BROWN CLAY W/ COARSE SAND STREAKS
202	213	LOOSE MED TO COARSE SAND & PEA GRAVEL
213	215	TIGHT MED TO COARSE SAND & PEA GRAVEL W/ CLAY
215	257	BROWN & LIGHT GREEN, CLAY W/ FINE SAND TO MED SAND STREAKS
257	262	FAIRLY LOOSE MED FINE SAND W/ SOME CLAY
262	285	BROWN CLAY W/ WHITE CLAY
285	298	VERY TIGHT MED FINE TO MED SAND W/ CLAY STREAKS

Form	WWC5
Contractor	Hydro Resources Mid Continent, Inc.
Well Owner	Ron Jantz
Doc ID	1139404

Litholgy

From	To	LithologicLog
298	339	LOOSE MED FINE TO MED SAND W/ CLAY STREAKS
339	350	FAIRLY FIRM/TIGHT FINE SAND & CLAY MIX
350	372	LOOSE MED TO MED COARSE SAND W/ CLAY STREAKS
372	400	HARD BROWN CLAY STONE & GRAY SHALE & RED CLAY
400	420	GRAY SHALE, SOME BROWN
5		