

WATER WELL RECORD Form WVC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 041 HASKELL | NW 1/4 SW 1/4 NW 1/4 | 17 | T 28 | S | R 31 | W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 6 1/2 NE, 6 1/4 N, 1/2 W & 1/4 N OF SUBLETTE

2 WATER WELL OWNER: WITHERS, LAWRENCE
 RRP, St. Address, Box #: ROUTE 1, BOX 68
 City, State, ZIP code: COPELAND, KS 67836
 Board of Agriculture, Division of Water Resources
 Application Number: 30,832

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 605 | ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 314 ft. below land surface measured on mo/day/yr 03/10/07
 Pump test data: Well water was 300 ft. after 4 hours pumping 1075 gpm
 Estimated Yield 1075 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 605 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 605 ft., Dia 20 in. to 543 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 364 ft. to 384 ft., From 491 ft. to 511 ft.
 From 305 ft. to 435 ft., From 544 ft. to 604 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 605 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHWEST How many feet? 1295

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SALT			
2	15	01 CLAY			
15	55	01 CLAY 31 CALICHE			
55	84	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
84	123	04 SANDY CLAY 05 SAND			
123	157	05 SAND 13 FINE GRAVEL			
157	183	05 SAND 11 GRAVEL			
183	204	05 SAND 01 CLAY			
204	305	04 SANDY CLAY			
305	313	07 FINE SAND 08 MEDIUM SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/07/07 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/13/07
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 041 HASKELL | NE 1/4 SE 1/4 NE 1/4 | 17 | T 28 S | R 31 W

2 WATER WELL OWNER: WITHERS, LAWRENCE
 RRD, St. Address, Box #: ROUTE 1, BOX 68 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: COPELAND, KS 67836- Application Number: 30,832

FROM	TO	LITHOLOGIC LOG
313	362	01 CLAY
362	403	05 SAND 13 FINE GRAVEL 01 CLAY
403	435	17 SAND & GRAVEL 20 LIMESTONE 01 CLAY
435	479	04 SANDY CLAY 20 LIMESTONE 05 SAND
479	493	04 SANDY CLAY 01 CLAY
493	500	07 FINE SAND 08 MEDIUM SAND
500	546	04 SANDY CLAY 20 LIMESTONE 05 SAND
546	575	01 CLAY
575	601	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND
601	611	05 SAND 11 GRAVEL
611	650	04 SANDY CLAY
650	683	31 CALICHE 10 SHALE
683	720	31 CALICHE 10 SHALE 20 LIMESTONE
		10 SHALE 31 CALICHE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/07/87 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/13/87
 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Benny J. Richman*