

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12-6-83 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/y) 12-13-83 under the business name of Heckle Drilling & Supply Co. by (signature) Charles Wymore

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

CUSTOMER'S NAME Emil Nightengale DATE 6/10/81
STREET ADDRESS _____ TEST # 1 E. LOG ues
CITY & STATE Sublette, KS 67877 DRILLER Mal
COUNTY Haskell QUARTER NW SECTION 6 TOWNSHIP 28 RANGE 31
LOCATION 1200' E of well Underground water line 15' S
Well location

%	FOOTAGE			DESCRIPTION OF STRATA	Static Water Level
	From	Pay	To		Proposed Well Depth
	0		3	TOP SOIL	
	3		19	BROWN CLAY	
	19		60	FINE SAND-FEW CLAY STKS	
	60		80	FINE SAND & SANDY CLAY	
	80		102	BROWN CLAY, SAND STKS	
	102		123	SAND-FINE TO MED COURSE SMALL TO LARGE GRAVEL	
	123		136	BROWN, WHITE & GRAY CLAY STICKY	
60	136	12	237	SAND-FINE TO MED COURSE SMALL TO MED GRAVEL FEW SANDY CLAY STKS	
	237		244	YELLOW CLAY SAND STKS	
70	244	25	269	SAND-FINE TO MED COURSE SMALL TO MED GRAVEL FEW LARGE	
	269		277	GRAY CLAY	
60	277	39	316	SAND-FINE TO MED COURSE SMALL GRAVEL	
	316		320	BROWN CLAY	
	320		345	BLUE & GRAY CLAY	
70	345	37	382	SAND-FINE TO MED COURSE SMALL & FEW MED GRAVEL	
				ROUGH IN PLACES	
	382		387	YELLOW & GRAY CLAY	
60	387	12	399	SAND-FINE TO MED COURSE SMALL GRAVEL, FEW CLAY STKS	
	399		420	BROWN & BROWN SANDY CLAY	
60	420	10	430	SAND-FINE TO MED COURSE SMALL GRAVEL	
	430		446	BROWN & TAN CLAY	
20	446	7	453	SAND-FINE LIMESTONE	
	453		465	BROWN CLAY STICKY	
	465		473	SAND-GRAY FINE & SANDY CLAY	
	473		500	BROWN & BROWN SANDY CLAY STICKY	
40	500	28	528	SAND-FINE & SMALL FEW MED FEW CLAY STKS	
60	528	8	536	SAND-FINE TO MED BROWN COURSE GRAVEL	
70	536	23	559	SAND-FINE TO MED COURSE BROWN & TAN ROCK FEW SMALL CLAY STKS	
	559		580	SOAPSTONE	
		201			
				3 SACKS QUIK-GEL	
				SET UP WEST PIT'S NORTH	
				WELL DEPTH - 562'	

GARDEN CITY, KS
Phone 226-3278

HENKLE DRILLING & SUPPLY CO., INC.
IRRIGATION HEADQUARTERS

SUBLETTE, KS
Phone 675-4311

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS