

DRILLERS TEST LOG

CUSTOMERS NAME Lawrence Withers DATE 5/12/78
 STREET ADDRESS _____ TEST # 1 E. LOG Yes
 CITY & STATE Copeland, Kansas DRILLER Martinez
 COUNTY Haskell QUARTER NW SECTION 16 TOWNSHIP 28 RANGE 31
 LOCATION 100 ft South of the NW corner of the 1/4.

WELL LOCATION

%	FOOTAGE			DESCRIPTION OF STRATA	Static Water Level _____
	From	Pay	To		Proposed Well Depth _____
	0		2	Top Soil	
	2		118	Brown clay	
	118		181	Sand fine to med coarse, small to med size gravel.	
	181		185	Brown clay	
	185		240	Sand fine to med coarse and small gravel. Loose - used water.	
	240		250	Brown clay	
50	250	11	261	Sand fine to med coarse. Loose - used water.	
	261		266	Brown clay	
60	266	54	320	Sand fine to med coarse and small gravel. Loose - used water.	
50	320	11	331	Sand fine to med coarse. Loose - used water.	
	331		335	Brown clay - sticky.	
	335		390	Blue clay - sticky.	
	390		402	Brown clay with a few limerock sts.	
55	402	08	410	Sand fine to med coarse with a few small gravel.	
				Loose - used water.	
	410		440	Brown clay with a few limerock sts.	
60	440	10	450	Sand fine to med coarse and small gravel. Loose - used water.	
	450		485	Brown clay with a few limerock sts.	
50	485	07	492	Sand fine to med coarse. Loose - used water.	
	492		540	Brown clay with a few limerock sts.	
	540		578	Brown sandy clay with a few fine sand sts.	
70	578	29	607	Sand fine to med coarse, small brown gravel with a few brown rock sts. Loose - used water.	
	607		609	Brown clay	
70	609	48	657	Sand fine to med coarse, small brown gravel with a few brown rock sts. Loose - used water.	
	657		660	Soapstone.	
		178			
					TOTAL DEPTH OF WELL 660'
					Set up facing North <u>East</u>
					Dig pit on the East <u>South</u>
					Used 4 QUIK GEL

GARDEN CITY, KS
 Phone 276-3278

HENKLE DRILLING & SUPPLY CO., INC.
 IRRIGATION HEADQUARTERS

SUBLETTE, KS
 Phone 675-4311

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * STOCK WELLS