

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Haskell		NE 1/4 NE 1/4 NE 1/4	30	T 28 S	R 31 E/W
Distance and direction from nearest town or city street address of well if located within city? 5 1/2 East on 56 HWY and 5 1/2 North from Sublette, KS					
2 WATER WELL OWNER:		Mr. Brent Schmidt			
RR#, St. Address, Box # :		Board of Agriculture, Division of Water Resources			
City, State, ZIP Code :		Copelan d, Kansas 67837		Application Number: ---	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 490 ft. ELEVATION: Slope			
		Depth(s) Groundwater Encountered 1. Not available ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 242 ft. below land surface measured on mo/day/yr May 15, 1991			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield 20 gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 10 in. to 490 ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No XX; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes XX No			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued XX Clamped
XX PVC		4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded
			7 Fiberglass		Threaded
Blank casing diameter 5 in. to 450 ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface 18 in., weight 2.8 lbs./ft. Wall thickness or gauge No. .265					
TYPE OF SCREEN OR PERFORATION MATERIAL: XXX PVC					
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	10 Asbestos-cement
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	11 Other (specify)
					12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot		3 Mill slot	5 Gauzed wrapped	XX Saw cut	11 None (open hole)
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes	
			7 Torch cut	10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 450 ft. to 490 ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 20 ft. to 490 ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout XX Bentonite 4 Other					
Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
XX Septic tank		4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines		5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines		6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
				13 Insecticide storage	
Direction from well? North		How many feet? 100			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Topsoil			
2	16	Clay			
16	91	Sandy Clay			
91	172	Large Sand			
172	191	Clay and Med. Sand			
191	261	Med. Sand			
261	290	Brown Clay w/Sand Strips			
290	294	Clay			
294	300	Med. Sand			
300	441	Blue Clay w/Stips of Sand			
441	490	Med. Sand			
Included in Report					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) May 20, 1991 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 252 This Water Well Record was completed on (mo/day/yr) May 30, 1991 under the business name of Friesen Windmill & Supply Inc. by (signature) <i>Cornie J. Friesen</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send to three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-7320. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					

6670871008-27