


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Haskell</b>	Fraction <b>5/2 SE 1/4 NW 1/4 SE 1/4</b>	Section number <b>34</b>	Township number <b>T 28 S R 31 E/W</b>	Range number
2. Distance and direction from nearest town or city: <b>1 mile north, 1/2 mile west, 1/2 mile north, 1/2 mile west of Copeland.</b>		3. Owner of well: <b>Forrest Tricky</b>		Box 11		
Street address of well location if in city: <b>039'</b>		City, state, zip code: <b>Copeland, Kansas</b>				
4. Locate with "X" in section below: 		Sketch map: <b>1379' North, 2039' west of SE corner of SE 1/4, Sec. 34, T28S, R31W, Haskell County, Kansas</b>		6. Bore hole dia. <b>28</b> in. Completion date <b>7-29-76</b> Well depth <b>296</b> ft.		
5. Type and color of material		From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
Top soil		0	3	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Tan clay		3	10	9. Casing: Material <b>Stl.</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>37</b> lbs./ft. Dia. <b>16</b> in. to <b>165</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>.219</b>		
Fine to coarse sand with clay streaks dirty		10	56	10. Screen: Manufacturer's name <b>Foster,</b> <b>Doerr</b> <b>Louver, nislslot</b> <b>16"</b> Type <input type="checkbox"/> Dia. <input type="checkbox"/> Slot/gauze <b>1/8"</b> Length <b>131</b> Set between <b>165</b> ft. and <b>296</b> ft. ft. and <input type="checkbox"/> ft.		
Fine to coarse sand		56	70	Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>5 mm</b>		
Tan clay		70	89	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>174</b> ft. below land surface Date <b>6-15-76</b>		
Fine to coarse sand clay streaks		89	106	12. Pumping level below land surfaces: <b>195</b> ft. after <b>3</b> hrs. pumping <b>1700</b> g.p.m. <b>197</b> ft. after <b>1</b> hrs. pumping <b>1800</b> g.p.m. Estimated maximum yield <b>2,000</b> g.p.m.		
Tan clay		106	116	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/> mo./day/yr.		
Fine to coarse sand		116	123	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> <input type="checkbox"/> Inches above grade		
Tan clay		123	132	15. Well grouted? <b>Yes</b> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.		
Fine to coarse sand, fine to med. gravel very small clay streaks		132	296	16. Nearest source of possible contamination: <b>Unk</b> ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Blue clay sand streaks		296	340	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Layne &amp; Bowler</b> Model number <b>12TL</b> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <b>260</b> ft. capacity <b>1400</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne Western Co., Inc. 102</b> Business name <b>Garden City, Kansas</b> License No. <input type="checkbox"/> Address <b>18 Nov 76</b> Signed <b>Authorized representative</b> Date <b>18 Nov 76</b>		