

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	NC W 1/2 E 1/2	14	T 28 S	R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SUBLETTE; APPX 8 MILES NORTH & 9 MILES EAST

2 WATER WELL OWNER: JACOB DIETZ TRUST
 RR#, St. Address, Box #: PO DRAWER C
 City, State, ZIP code: PRATT, KS 67124-1103
 Board of Agriculture, Division of Water Resources
 Application Number: 18,497

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	NW	NE
M		
i		
l		
e		
	SW	SE

4 DEPTH OF COMPLETED WELL 648 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 312 ft. below land surface measured on mo/day/yr 04/05/05
 Pump test data: Well water was 374 ft. after 4 hours pumping 1470 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 648 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 648 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 433 ft. to 643 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 648 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 1305

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	76	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND			
76	91	05 SAND			
91	96	04 SANDY CLAY			
96	101	07 FINE SAND 08 MEDIUM SAND			
101	111	04 SANDY CLAY			
111	157	05 SAND 13 FINE GRAVEL 01 CLAY			
157	166	04 SANDY CLAY			
166	297	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
297	310	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/30/05 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/12/05
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	NC 1/4 W 1/2 1/4 E 1/2 1/4	14	T 28 S	R 31 W

2 WATER WELL OWNER: JACOB DIETZ TRUST

RR#, St. Address, Box # : PO DRAWER C

City, State, ZIP code : PRATT, KS 67124-1103

Board of Agriculture, Division of Water Resources

Application Number: 18,497

FROM	TO	LITHOLOGIC LOG
310	387	05 SAND 13 FINE GRAVEL
387	390	04 SANDY CLAY
390	396	05 SAND
396	428	01 CLAY
428	447	05 SAND
447	450	04 SANDY CLAY
450	467	07 FINE SAND 08 MEDIUM SAND
467	474	05 SAND
474	483	05 SAND
483	492	04 SANDY CLAY 05 SAND
492	508	05 SAND
508	511	01 CLAY
511	576	07 FINE SAND 08 MEDIUM SAND 01 CLAY
576	643	05 SAND 28 ROCK
643	662	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/30/05 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

under the business name of HENKLE DRILLING & SUPPLY

This Water Well Record was completed on (mo/day/yr) 04/12/05

by (signature)

Bruce J. Henkle