

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SE 1/4 SE 1/4 NE 1/4	30	T 28 S	R 31 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM SUBLETTE; APPX 6 3/4 MILES NORTH & 4 3/4 MILES EAST

2 WATER WELL OWNER: JEAN M. KOBLLING  
 RR#, St. Address, Box #: 2006 LAMESA DR  
 City, State, ZIP code: DODGE CITY, KS 67801-6432  
 Board of Agriculture, Division of Water Resources  
 Application Number: 20,019 & 9,593

3 LOCATE WELL'S LOCATION WITH  
 AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M				
i	W			X E
l				
e				
/ \				
	---	SW	---	SE

4 DEPTH OF COMPLETED WELL 620 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 322 ft. below land surface measured on mo/day/yr 04/12/05  
 Pump test data: Well water was 440 ft. after 4 hours pumping 600 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 620 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 620 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 420 ft. to 470 ft.,	From 528 ft. to 598 ft.
	From 485 ft. to 515 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 620 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	82	01 CLAY 31 CALICHE 05 SAND			
82	107	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
107	150	05 SAND 13 FINE GRAVEL			
150	207	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
207	244	05 SAND 11 GRAVEL			
244	250	01 CLAY 20 LIMESTONE			
250	258	05 SAND			
258	265	01 CLAY			
265	270	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/05/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/22/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SE 1/4 SE 1/4 NE 1/4	30	T 28 S	R 31 W

2 WATER WELL OWNER: JEAN M. KOELLING

RR#, St. Address, Box # : 2006 LAMESA DR

City, State, ZIP code : DODGE CITY, KS 67801-6432

Board of Agriculture, Division of Water Resources

Application Number: 20,019 & 9,593

FROM	TO	LITHOLOGIC LOG
270	329	01 CLAY 05 SAND
329	341	05 SAND 01 CLAY
341	370	01 CLAY 05 SAND
370	400	05 SAND 01 CLAY
400	440	05 SAND 01 CLAY
440	465	05 SAND 13 FINE GRAVEL 01 CLAY
465	481	04 SANDY CLAY 20 LIMESTONE 05 SAND
481	505	05 SAND 01 CLAY
505	515	07 FINE SAND 01 CLAY
515	525	01 CLAY
525	565	01 CLAY 05 SAND
565	582	07 FINE SAND 01 CLAY
582	598	05 SAND 13 FINE GRAVEL 28 ROCK
598	607	31 CALICHE
607	662	19 SHALE 20 LIMESTONE
662	679	19 SHALE 23 SANDSTONE 20 LIMESTONE
679	700	19 SHALE 31 CALICHE 20 LIMESTONE
700	730	19 SHALE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/05/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/22/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

*Bern Reichman*