

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL SW 1/4 SW 1/4 NE 1/4 14 T 28 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 5 MILES N, 2 W, 3 N, 1/2 E, 1/2 N OF SUBLETTE

2 WATER WELL OWNER: STONESTREET, JOHN

RR#, St. Address, Box #: RT 1 BOX 50

Board of Agriculture, Division of Water Resources

City, State, ZIP code: KISMET, KS 67859-

Application Number: 26,334

3 LOCATE WELL'S LOCATION WITH

AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 572

ELEVATION: 0

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 317 ft. below land surface measured on mo/day/yr 04/14/98

Pump test data: Well water was 505 ft. after 4 hours pumping 945 gpm

Estimated Yield 945 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 572 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;

If yes, mo/day/yr sample was submitted

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 572 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 420 ft. to 570 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 572 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? SOUTH

How many feet? 200

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	15	01 CLAY			
15	75	01 CLAY 04 SANDY CLAY 31 CALICHE			
15	75	05 SAND			
75	93	05 SAND 11 GRAVEL			
93	107	04 SANDY CLAY 05 SAND 20 LIMESTONE			
107	237	05 SAND 11 GRAVEL			
237	257	01 CLAY 04 SANDY CLAY 05 SAND			
257	283	05 SAND 11 GRAVEL			
283	290	01 CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was

completed on (mo/day/year) 04/10/98 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 04/24/98

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SW 1/4 SW 1/4 NE 1/4	14	T 28 S	R 32 W

2 WATER WELL OWNER: STONESTREET, JOHN
RR#, St. Address, Box #: RT 1 BOX 50
Board of Agriculture, Division of Water Resources

City, State, ZIP code : KISMET, KS 67859-
Application Number: 26,334

FROM	TO	LITHOLOGIC LOG
290	410	01 CLAY
410	420	01 CLAY 05 SAND
420	438	05 SAND 11 GRAVEL 01 CLAY
438	456	05 SAND 11 GRAVEL 01 CLAY
456	470	05 SAND 01 CLAY
470	483	04 SANDY CLAY 05 SAND 28 ROCK
483	510	05 SAND 01 CLAY
510	525	05 SAND 23 SANDSTONE
525	534	05 SAND
534	544	01 CLAY
544	569	23 SANDSTONE
569	573	20 LIMESTONE
573	585	19 SHALE 28 ROCK
585	620	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/10/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/24/98 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce Reichman