

WATER WELL RECORD Form WWC-5 KSA 82a-1212

11 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
COUNTY: 041 HASKELL		NW 1/4 NW 1/4 SE 1/4		14		T 28 S		R 32 W	
Distance and direction from nearest town or city street address of well if located within city?									
APPROX. 8 MILES NORTH, 2 1/2 EAST, & 1/2 NORTH OF SUBLETTE									
12 WATER WELL OWNER:		STONESTREET INVESTMENTS							
RD#, St. Address, Box #:		8500 W. 116TH STREET				Board of Agriculture, Division of Water Resources			
City, State, ZIP code:		OVERLAND PARK, KS 66210-				Application Number: 26,334			
13 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 543		ELEVATION: 0					
		Depth(s) Groundwater Encountered		1. 0 ft. 2. 0 ft. 3. 0 ft.					
1/4		WELL'S STATIC WATER LEVEL 316 ft. below land surface measured on mo/day/yr 04/28/97							
		Pump test data: Well water was 474 ft. after 4 hours pumping 655 gpm							
NW NE		Estimated Yield 655 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm							
E		Bore Hole Diameter 24 in. to 543 ft., and in. to 0 ft.							
SE		WELL WATER TO BE USED AS: 02 IRRIGATION							
Was a chemical/bacteriological sample submitted to department? No									
If yes, mo/day/yr sample was submitted		Water well disinfected? Yes							
15 TYPE OF BLANK CASING USED: 01 STEEL		CASING JOINTS: WELDED							
Blank casing diameter 16 in. to 543 ft., Dia in. to 0 ft., Dia in. to 0 ft.									
Casing height above land surf. 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250									
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL									
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT									
SCREEN PERFORATED INTERVALS:		From 410 ft. to 540 ft., From 0 ft. to 0 ft.							
		From 0 ft. to 0 ft., From 0 ft. to 0 ft.							
GRAVEL PACK INTERVALS:		From 20 ft. to 480 ft., From 0 ft. to 0 ft.							
		From 480 ft. to 543 ft., From 0 ft. to 0 ft.							
16 GROUT MATERIAL 03 BENTONITE									
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.									
What is the nearest source of possible contamination: 14 ABAND. WELL									
Direction from well? NORTHEAST		How many feet? 279							
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS				
0	2	02 SILT							
2	63	04 SANDY CLAY 31 CALICHE 05 SAND							
63	94	05 SAND 01 CLAY 11 GRAVEL							
94	102	04 SANDY CLAY 05 SAND							
102	143	05 SAND 01 CLAY 11 GRAVEL							
143	243	05 SAND 11 GRAVEL 01 CLAY							
243	251	04 SANDY CLAY							
251	260	05 SAND							
260	278	05 SAND 11 GRAVEL							
278	306	04 SANDY CLAY 05 SAND							
17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was									
completed on (mo/day/year) 04/10/97 and this record is true to the best of my knowledge and belief. Kansas									
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/15/97									
under the business name of HENKLE DRILLING & SUPPLY by (signature)									

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 041 HASKELL | NW 1/4 NW 1/4 SE | 14 | T 28 S | R 32 W

2 WATER WELL OWNER: STONESTREET INVESTMENTS
RR#, Address, Box #: 8500 W. 116TH STREET
City, State, ZIP: OVERLAND PARK, KS 66210

Board of Agriculture, Division of Water Resources
Application Number: 26,334

FROM	TO	LITHOLOGIC LOG
306	340	01 CLAY
340	407	01 CLAY
407	435	05 SAND 11 GRAVEL
435	470	05 SAND 11 GRAVEL 01 CLAY
470	477	04 SANDY CLAY 20 LIMESTONE 05 SAND
477	498	17 SAND & GRAVL 01 CLAY 20 LIMESTONE
498	540	05 SAND 04 SANDY CLAY
540	557	01 CLAY 31 CALICHE
557	580	19 SHALE

3 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 04/10/97 and this record is true to the best of my knowledge and belief. Kansas
Water Well Completion Number: 145 This Water Well Record was completed on (mo/day/yr) 05/15/97
under the business name of HUNKLE DRILLING & SUPPLY

By (signature)

Bruce J. Richmond