

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL SE 1/4 SE 1/4 NE 1/4 04 T 28 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 12 MILES NORTH, 3 WEST AND 1/2 SOUTH OF SUBLETTE

2 WATER WELL OWNER: KELLS, DON
 RR#, St. Address, Box #: RR 1, BOX 94A Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SATANTA, KS 67870- Application Number: 16,955

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 619 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 386 ft. below land surface measured on mo/day/yr 7/28/95
 Pump test data: Well water was 482 ft. after 24 hours pumping 1075 gpm
 Estimated Yield 1075 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 619 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 619 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 412 ft. to 554 ft., From 0 ft. to 0 ft.
 From 589 ft. to 609 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 619 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTH How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	23	04 SANDY CLAY 31 CALICHE			
23	83	07 FINE SAND 01 CLAY			
83	101	05 SAND 11 GRAVEL 04 SANDY CLAY			
101	123	05 SAND 13 FINE GRAVEL 15 CRS GRAVEL			
123	257	05 SAND 04 SANDY CLAY 11 GRAVEL			
257	263	01 CLAY 05 SAND			
263	309	01 CLAY 07 FINE SAND			
309	341	04 SANDY CLAY 05 SAND			
341	346	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/25/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/31/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 041 HASKELL | SE 1/4 SE 1/4 NE 1/4 | 04 | T 28 S | R 33 W

2 WATER WELL OWNER: KELLS, DON
RR#, St. Address, Box # : RR 1, BOX 94A
City, State, ZIP code : SATANTA, KS 67870-

Board of Agriculture, Division of Water Resources
Application Number: 16,955

FROM	TO	LITHOLOGIC LOG
346	364	01 CLAY
364	427	05 SAND 07 FINE SAND 15 CRS GRAVEL
427	483	07 FINE SAND 08 MEDIUM SAND
483	522	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
522	591	01 CLAY
591	607	07 FINE SAND 08 MEDIUM SAND 28 ROCK
607	656	01 CLAY 31 CALICHE
656	660	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/25/95 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/31/95
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce J. Reichmuth