



# DRILLERS TEST LOG

CUSTOMERS NAME Forrest Cox DATE 12/14/77  
 STREET ADDRESS \_\_\_\_\_ TEST # 1 E. LOG Yes  
 CITY & STATE Sublette, Kansas DRILLER Rector  
 COUNTY Haskell QUARTER SE SECTION 8 TOWNSHIP 28 RANGE 33  
 LOCATION 1180' West of the SE corner of the 1/4.

				WELL LOCATION	
%	FOOTAGE			DESCRIPTION OF STRATA	Static Water Level _____
	From	Pay	To		Proposed Well Depth _____
	0		3	Top Soil	
	3		45	Brown sandy clay	
	45		65	Brown clay and caliche.	
	65		195	Sand fine to med coarse, small to large gravel.	
				Used alot of water. Mud was heavy.	
	195		245	Brown clay, caliche and sand sts.	
	245		260	Brown clay and sand sts.	
	260		280	Sand fine to med coarse, small gravel and clay sts.	
	280		298	Blue clay - sticky	
	298		304	Sand fine to med coarse with small to med gravel.	
	304		325	Blue clay and sand sts.	
	325		338	Sand fine to med coarse, small gravel with sandy clay. Used alittle water. Mud was heavy.	
40	338	12	350	Sand, limerock and clay. Drilled firm.	
65	350	15	365	Sand fine to med coarse, small gravel. Drilled ragged. Used water.	
	365		375	Brown clay - sticky.	
65	375	15	390	Sand fine to med coarse, small gravel. Had a few clay and limerock sts.	
	390		400	Brown clay and limerock.	
60	400	05	405	Sand fine to med coarse. Small gravel.	
	405		420	Brown clay and limerock.	
65	420	44	464	Sand fine to med coarse, small gravel. Some clay & limerock. Drilled firm. Used alot of water.	
	464		476	Brown clay - sticky.	
50	476	9	485	Sand fine to med coarse with a few med to small gravel.	
	485		540	Brown clay and limerock - clay was sticky.	
55	540	5	545	Sand, brown rock and brown clay. Used water.	
	545		560	Brown clay, sts of red shale and soapstone.	
		105			
				TOTAL DEPTH OF WELL — 550'	
				Set up facing West	
				Pit on the North	

GARDEN CITY, KS  
 Phone 276-3278

HENKLE DRILLING & SUPPLY CO., INC.  
 IRRIGATION HEADQUARTERS

SUBLETTE, KS  
 Phone 675-4311

TEST HOLES \* \* \* \* \* IRRIGATION & INDUSTRIAL WELLS \* \* \* \* STOCK WELLS