

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NE 1/4 NE 1/4 SW 1/4 14 T 28 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3.0 MILES WEST AND 8.5 MILES NORTH OF SUBLETTE.

2 WATER WELL OWNER: FORREST COX
 RR#, St. Address, Box #: HCR 1, BOX 34 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SUBLETTE, KS 67877- Application Number: 27,297

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

WELL'S STATIC WATER LEVEL 368 ft. below land surface measured on mo/day/yr 02/24/92
 Pump test data: Well water was 433 ft. after 4 hours pumping 1057 gpm
 Estimated Yield 0 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 30 in. to 619 ft., and 24 in. to 755 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 385 ft., Dia 20 in. to 588 ft., Dia 16 in. to 750 ft.
 Casing height above land surface 12 in., weight 53 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 386 ft. to 426 ft., From 480 ft. to 490 ft.
 From 427 ft. to 467 ft., From 512 ft. to 532 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 750 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: IRRIGATION WELL
 Direction from well? EAST How many feet? 280

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	01 CLAY			
3	71	04 SANDY CLAY 31 CALICHE			
71	93	07 FINE SAND 08 MEDIUM SAND 15 CRS GRAVEL			
93	101	01 CLAY			
101	147	07 FINE SAND 08 MEDIUM SAND 15 CRS GRAVEL			
147	153	01 CLAY			
153	236	05 SAND 15 CRS GRAVEL 01 CLAY			
236	245	01 CLAY			
245	296	01 CLAY			
296	300	05 SAND 14 MED GRAVEL 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/21/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/21/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas B. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NE 1/4 NE 1/4 SW 1/4 14 T 28 S R 33 W

2 WATER WELL OWNER: FORREST COX
 RR#, St. Address, Box #: HCR 1, BOX 34 Board of Agriculture, Division of Water Resources

City, State, ZIP code : SUBLETTE, KS 67877- Application Number: 27,297

SCREEN PERFORATED INTERVALS: From 539 ft. to 549 ft., From 660 ft. to 680 ft. 727 ft. to 747 ft.
 From 550 ft. to 570 ft., From 690 ft. to 710 ft.

FROM	TO	LITHOLOGIC LOG
300	370	05 SAND 20 LIMESTONE 35 CLAY & GRAVL
370	400	05 SAND 20 LIMESTONE 35 CLAY & GRAVL
400	415	05 SAND 13 FINE GRAVEL
415	419	04 SANDY CLAY 20 LIMESTONE
419	440	05 SAND 13 FINE GRAVEL
440	467	05 SAND 07 FINE SAND
467	481	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
481	488	06 VERY FN SAND 07 FINE SAND
488	510	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
510	520	06 VERY FN SAND 07 FINE SAND
520	532	05 SAND 28 ROCK
532	540	04 SANDY CLAY 19 SHALE
540	565	19 SHALE 23 SANDSTONE 28 ROCK
565	571	19 SHALE 20 LIMESTONE
571	660	19 SHALE 20 LIMESTONE
660	680	19 SHALE 23 SANDSTONE
680	693	19 SHALE 20 LIMESTONE
693	708	19 SHALE 23 SANDSTONE
708	727	19 SHALE 20 LIMESTONE
727	746	23 SANDSTONE 19 SHALE
746	750	19 SHALE 20 LIMESTONE
750	760	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/21/92 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/21/92
 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas R. Henkle*