



## DRILLERS TEST LOG

**CUSTOMER'S NAME:** Kent Ochs

DATE: 7/18/88

**STREET ADDRESS:** RR #1, Box 15A

TEST #	1	E. LOG Yes
--------	---	------------

**CITY & STATE:** Sublette, Ks. 67877

**DRILLER** Sheldon

COUNTY	Haskell	QUARTER	NE	SECTION	25	TOWNSHIP	28	RANGE	33
--------	---------	---------	----	---------	----	----------	----	-------	----

**LOCATION** 500' East of the Northwest Corner of the NE<sup>1</sup>/<sub>4</sub>.

Z	FOOTAGE			DESCRIPTION OF STRATA	STATIC WATER LEVEL: _____	
	From	Pay	TO		Proposed Well Depth:	
	0		2	Top soil.		
	2		67	Brown sandy clay.		
	67		198	Sand fine to medium coarse with few small gravel, & with few brown clay streaks.		
	198		210	Brown sandy clay.		
	210		274	Blue clay.		
	274		335	Sand fine to medium coarse.		
60	335	78	398	Sand fine to medium with few clay streaks.		
65	398	22	419	Sand fine to medium coarse. Some small gravel.		
	419		442	Brown sandy clay.		
60	442	34	476	Sand fine to medium coarse with few clay streaks.		
	476		519	Brown sandy clay with few fine sand streaks.		
60	519	18	537	Sand fine to medium coarse.		
70	537	14	551	Sand fine to medium coarse. Brown rock. Small to medium brown gravel.		
	551		555	Brown sandy clay.		
60	555	23	578	Sand fine to medium coarse with few clay streaks.		
	578		600	Yellow soapstone & Limestone ledges		
				5" PVC		
					PERF	PLAIN
				575 - 535	40'	
				535 - 475		60'
				475 - 455	20'	
				455 - 425		30'
				425 - 385	40'	
				385 - 0		385'
				Total	160'	475'
				5 - 50# sacks - Hi-Tek		
				6 - 50# sacks - Hole plug		
				2 - 5" Caps		

GARDEN CITY, KS 67846  
3795 West Jones Ave.

HENKLE DRILLING & SUPPLY CO., INC.

316-277-2389

## IRRIGATION HEADQUARTERS

TEST HOLES \* \* \* \* \* IRRIGATION & INDUSTRIAL WELLS \* \* \* \* \* STOCK WELLS