

T		R		EW		sec	1/4	1/4	1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

DRILLERS TEST LOG

CUSTOMERS NAME Jerald Trimpa DATE 4-11-75
 STREET ADDRESS RFD # 1 TEST # 1 E. Log Hole
 CITY & STATE Sublette, Kansas DRILLER Henderhan
 COUNTY Haskell QUARTER NW SECTION 28 TOWNSHIP 28 RANGE 33

LOCATION 300 Ft. North of the SW corner of the NW $\frac{1}{4}$

WELL LOCATION

%	DRILLED from	FOOTAGE Pay to	Description of Strata	Static Water Level 265' Proposed Well Depth
	0	2	Top soil	
	2	52	Brown clay, sandy clay, limerock ledges, fine sand st.	
	52	60	Sand fine to med., some coarse, loose,	
	60	100	Sand, fine med. coarse, some, small gravel. Brown gravel. Rough in places. Loose in places. Few clay st.	
	100	164	Sand fine med. coarse, small med. large gravel. Brown gravel. Rough drilled. Used water.	
	164	193	Brown clay, rock ledges.	
	192	220	Brown and blue clay and sand st. Mixed, hard ledges.	
	220	265	Blue clay	
	265	301	Blue clay, few yellow clay st. Few sand st. Sticky. in places. Few limerock ledges.	
60	301	15 316	Sand fine med. coarse, small gravel. Some brown gravel. Limerock ledges, some clay st.	
	316	323	Brown clay, sticky	
60	323	79 402	Sand fine to med. coarse, small gravel. Brown and tan gravel. Very hard limerock and cemented ledges. Used water.	
	402	405	Brown sandy clay	
65	405	21 426	Sand fine med. coarse, small, some med. gravel. Brown gravel. Loose. Hard ledges. Used water. Some clay st.	
	426	444	Brown clay and sandy clay, sticky in places. Limerock ledges.	
65	444	9 453	Sand fine med. coarse, small gravel. Brown gravel. Loose. Hard in places. Used water.	
	453	509	Brown sandy clay, limerock ledges, sand st. Drills sticky in places.	
45	509	11 520	Sand fine to med. clay st. Limerock ledges.	
	520	523	Brown clay and limerock ledges.	
70	523	23 546	Sand fine med. coarse, small med. gravel. Brown & tan gravel. Hard ledges 440' to 446'. Used water. Drills rough.	
	546	560	Brown and yellow clay, hard ledges, sticky in places.	
	560	600	Brown clay, limerock and blue shale	
				TOTAL DEPTH OF WELL 560 Ft.
				SET UP NORTH: DIG PIT ON THE EAST.

ARDEN CITY, KANSAS HENKLE DRILLING & SUPPLY CO., INC. SUBLETTE, KANSAS
 HONE 276-3278 IRRIGATION HEADQUARTERS PHONE 675-4311
 EST HOLES*****STOCK WELLS*****IRRIGATION AND INDUSTRIAL WELLS*****