

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SW 1/4 SE 1/4 NW 1/4	36	T 28 S	R 33 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX 1 1/2 MILES WEST, 5 1/2 NORTH, 1/4 WEST OF SUBLETTE2 WATER WELL OWNER: **OLD SANTA FE FEEDERS INC**RR#, St. Address, Box #: **HC 1 BOX 14**

Board of Agriculture, Division of Water Resources

City, State, ZIP code : **SUBLETTE, KS 67877-9708**Application Number: **24,566**3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \				
1	NW		NE	
M		X		
i	W			E
1				
e		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL **603** ELEVATION: **0**Depth(s) Groundwater Encountered 1. **0 ft.** 2. **0 ft.** 3. **0 ft.**WELL'S STATIC WATER LEVEL **372** ft. below land surface measured on mo/day/yr **08/19/98**Pump test data: Well water was **0 ft.** after **0** hours pumping **0** gpmEstimated Yield **200** gpm: Well water was **0 ft.** after **0** hours pumping **0** gpmBore Hole Diameter **17.5** in. to **603** ft., and in. to **0** ft.WELL WATER TO BE USED AS: **03 FEEDLOT**Was a chemical/bacteriological sample submitted to department? **No** ;If yes, mo/day/yr sample was submitted Water well disinfected? **Yes**5 TYPE OF BLANK CASING USED: **02 PVC**CASING JOINTS: **GLUED**Blank casing diameter **8 5 8** in. to **590** ft., Dia in. to **0** ft., Dia in. to **0** ft.Casing height above land surface **12** in., weight **7** lbs/ft. Wall thickness or gauge No. **.410**TYPE OF SCREEN OR PERFORATION MATERIAL: **07 PVC**SCREEN OR PERFORATION OPENINGS ARE: **03 MILL SLOT**SCREEN PERFORATED INTERVALS: From **410** ft. to **450** ft., From **0** ft. to **0** ft.From **510** ft. to **590** ft., From **0** ft. to **0** ft.GRAVEL PACK INTERVALS: From **25** ft. to **603** ft., From **0** ft. to **0** ft.From **0** ft. to **0** ft., From **0** ft. to **0** ft.6 GROUT MATERIAL **03 BENTONITE**Grout Intervals: From **5** ft. to **25** ft., From **0** ft. to **0** ft., From **0** ft. to **0** ft.What is the nearest source of possible contamination: **NONE OBSERVED**

Direction from well?

How many feet? **0**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	25	04 SANDY CLAY 31 CALICHE			
25	45	04 SANDY CLAY 05 SAND			
45	51	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
51	64	04 SANDY CLAY 05 SAND			
64	89	17 SAND & GRAVL 30 ROCK & CLAY 11 GRAVEL			
89	100	01 CLAY 20 LIMESTONE			
100	316	05 SAND 11 GRAVEL			
316	367	01 CLAY			
367	390	04 SANDY CLAY 11 GRAVEL 04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and wascompleted on (mo/day/year) **07/17/98** and this record is true to the best of my knowledge and belief. KansasWater Well Contractor's License No. **145**This Water Well Record was completed on (mo/day/yr) **08/18/98**under the business name of **HENKLE DRILLING & SUPPLY**

by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SW 1/4 SE 1/4 NW 1/4	36	T 28 S	R 33 W

2 WATER WELL OWNER: OLD SANTA FE FEEDERS INC

RR#, St. Address, Box # : HC 1 BOX 14

Board of Agriculture, Division of Water Resources

City, State, ZIP code : SUBLETTE, KS 67877-9708

Application Number: 24,566

FROM	TO	LITHOLOGIC LOG
390	414	11 GRAVEL 04 SANDY CLAY
414	420	13 FINE GRAVEL 14 MED GRAVEL 01 CLAY
420	430	13 FINE GRAVEL 14 MED GRAVEL
430	435	05 SAND 01 CLAY
435	515	01 CLAY 13 FINE GRAVEL 14 MED GRAVEL
515	585	13 FINE GRAVEL 14 MED GRAVEL 28 ROCK
585	590	31 CALICHE
590	603	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/17/98 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 08/18/98

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce Richmond