

WATER WELL RECORD Form WWC-5

Division of Water Resources App. No.

Well ID

Original Record Correction Change in Well Use

1 LOCATION OF WATER WELL: County: Grant Fraction SW 1/4 NW 1/4 SE 1/4 SW 1/4 Section Number 16 Township Number T 28 S Range Number R 37 E W

2 WELL OWNER: Last Name: Fransisco First: Barbosa Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here:

3 LOCATE WELL WITH 'X' IN SECTION BOX: N W E S 1 mile. 4 DEPTH OF COMPLETED WELL: 380 ft. Depth(s) Groundwater Encountered: 1) 240 ft. 2) ... 3) ... 4) Dry Well. WELL'S STATIC WATER LEVEL: 240 ft. 5 Latitude: 37.607900 Longitude: 101.376137

7 WELL WATER TO BE USED AS: 1. Domestic: Household, Lawn & Garden, Livestock. 2. Irrigation. 3. Feedlot. 4. Industrial. 5. Public Water Supply. 6. Dewatering. 7. Aquifer Recharge. 8. Monitoring. 9. Environmental Remediation. 10. Oil Field Water Supply. 11. Test Hole. 12. Geothermal. 13. Other.

Was a chemical/bacteriological sample submitted to KDHE? Yes No. Water well disinfected? Yes No.

8 TYPE OF CASING USED: Steel PVC Other. CASING JOINTS: Glued Clamped Welded Threaded. Casing diameter 6 in. to 380 ft. Casing height above land surface 18 in. TYPE OF SCREEN OR PERFORATION MATERIAL: Steel Stainless Steel PVC Other. SCREEN OR PERFORATION OPENINGS ARE: Continuous Slot Mill Slot Gauze Wrapped Torch Cut Drilled Holes Other. Louvered Shutter Key Punched Wire Wrapped Saw Cut None.

9 GROUT MATERIAL: Neat cement Cement grout Bentonite Other. Grout Intervals: From 5 ft. to 40 ft. Nearest source of possible contamination: No potential source of contamination within 200 ft.

10 FROM TO LITHOLOGIC LOG FROM TO LITHO. LOG (cont.) or PLUGGING INTERVALS. Attached Attached Attached. Notes:

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed, reconstructed, or plugged under my jurisdiction and was completed on (mo-day-year) 10/07/2020 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 846. This Water Well Record was completed on (mo-day-year) 10/09/2020 under the business name of Nash Water Well Service, LLC.

Form	WWC5
Contractor	Nash Water Well Service, LLC
Well Owner	Barbosa Fransisco
Doc ID	1532742

Lithology

Depth (ft)	To (ft)	Lithology
0	50	TOP SOIL FINE SAND TAN BROWN CLAY
50	60	FINE COARSE SAND WITH SMALL TO LARGE GRAVEL STREAKS WITH TAN CLAY STREAKS & LAYERS
60	85	TAN CLAY
85	120	TAN CLAY WITH FINE MEDIUM SAND STREAKS & LAYERS
120	140	TAN GRAY CLAY WITH FINE SAND STREAKS
140	180	FINE MEDIUM SAND WITH TAN GRAY CLAY
180	230	TAN CLAY WITH FINE SAND
230	240	FINE COARSE SAND WITH CLAY
240	260	FINE COARSE SAND
260	290	TAN STICKY CLAY WITH FINE SAND
290	320	FINE SAND WITH TAN CLAY
320	347	FINE COARSE SAND WITH TAN CLAY STREAKS
347	353	TAN YELLOW STICKY CLAY WITH FINE SAND STREAKS
353	360	FINE SAND TAN CLAY
360	385	PURPLE TAN GRAY BLUE CLAY WITH FINE SAND STREAKS

Form	WWC5
Contractor	Nash Water Well Service, LLC
Well Owner	Barbosa Fransisco
Doc ID	1532742

Lithology

From	To	LithologicLog
360	400	BLUE CLAY