

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number |
 COUNTY: 034 GRANT | NW 1/4 NW 1/4 NW 1/4 | 08 | T 28 S | R 38 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 MILES NORTH & 7 3/4 MILES WEST OF ULYSSES

2 WATER WELL OWNER: DYCK, EDWARD A.
 RR#, St. Address, Box #: P. O. BOX 913 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUTCHINSON, KS 67504- Application Number: GT21

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 620 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \		WELL'S STATIC WATER LEVEL 251 ft. below land surface measured on mo/day/yr 05/10/96	
t		Pump test data: Well water was 290 ft. after 4 hours pumping 1200 gpm	
M		Estimated Yield 1200 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm	
i		Bore Hole Diameter 24 in. to 620 ft., and in. to 0 ft.	
e		WELL WATER TO BE USED AS: 02 IRRIGATION	
\ /		Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes	

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 620 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. 0250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 270 ft. to 290 ft., From 393 ft. to 413 ft.
 From 345 ft. to 385 ft., From 419 ft. to 429 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 430 ft., From 0 ft. to 0 ft.
 From 430 ft. to 620 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 275

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	40	04 SANDY CLAY			
40	62	01 CLAY			
62	90	08 MEDIUM SAND			
90	185	01 CLAY			
185	220	01 CLAY 05 SAND			
220	240	01 CLAY 20 LIMESTONE			
240	287	08 MEDIUM SAND 09 COARSE SAND 01 CLAY			
287	337	01 CLAY 07 FINE SAND			
337	350	07 FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 05/08/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/16/96 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 034 GRANT	NW 1/4 NW 1/4 NW 1/4	08	T 28 S	R 38 W

2 WATER WELL OWNER:	DYCK, EDWARD A.	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	P. O. BOX 913	Application Number: GT21
City, State, ZIP code :	HUTCHINSON, KS 67504-	

SCREEN PERFORATED INTERVALS:	From 457 ft. to 617 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
350	358	01 CLAY 05 SAND
358	385	07 FINE SAND 08 MEDIUM SAND 01 CLAY
385	395	01 CLAY
395	410	09 COARSE SAND
410	418	01 CLAY
418	430	23 SANDSTONE
430	450	19 SHALE
450	480	19 SHALE 23 SANDSTONE
480	538	19 SHALE 23 SANDSTONE
538	596	19 SHALE 23 SANDSTONE
596	617	19 SHALE 23 SANDSTONE
617	625	28 ROCK

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/08/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/16/96 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruno J. Reichert