

MW14

1 LOCATION OF WATER WELL: County: SEDGWICK		Fraction NW 1/4 NW 1/4 SE 1/4	Section Number 8	Township Number T 28 S	Range Number R 4W E/W
Distance and direction from nearest town or city street address of well if located within city? Northwest corner of South Main Street & South Avenue - Cheney					
2 WATER WELL OWNER: Farmers Co-op Elevator Company RR#, St. Address, Box # : PO Box 340 City, State, ZIP Code : Cheney KS 67025					
Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 35.25 ft. ELEVATION: 67025			
		Depth(s) Groundwater Encountered 1 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL 15.02 ft. below land surface measured on mo/day/yr 7/20/04 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No ☒			
		5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped 3 PVC 4 ABS 7 Fiberglass 9 Other (specify below) Welded Blank casing diameter 2 in. to 25.25 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 35.5 in., weight lbs./ft. Wall thickness or gauge No. 5/16 40 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass 7 PVC 10 Asbestos-Cement 2 Brass 4 Galvanized Steel 6 Concrete tile 8 RMP (SR) 11 Other (Specify) 9 ABS 12 None used (open hole)			
		SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 10/20 5 Guazed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) ft.			
SCREEN-PERFORATED INTERVALS: From 25.25 ft. to 35.25 ft., From ft. to ft. From ft. to ft., From ft. to ft.		GRAVEL PACK INTERVALS: From 23.7 ft. to 25.25 ft., From ft. to ft. From ft. to ft., From ft. to ft.			
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 2 ft. to 23.7 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) Direction from well? immediate vicinity How many feet? Runoff from parking area					
FROM TO LITHOLOGIC LOG			FROM TO PLUGGING INTERVALS		
0	5	Clay	0	1	Cement cap
5	15	Sand	1	2	Top soil
15	35.25	Red & green shale w/sand	2	23.7	3/8 Bentonite chips
			23.7	35.25	10/20 sand

RECEIVED
SEP 03 2004
BUREAU OF WATER

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was **(1)** constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **7/13/04** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No **665** This Water Well Record was completed on (mo/day/yr) **8/14/04** under the business name of **Earth Well Environmental** by (signature) *Steven E. Gill*