

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County: <u>Sedgwick</u>	Fraction: <u>SW 1/4 NW 1/4</u>	Section number: <u>4</u>	Township number: <u>T 28 S</u>	Range number: <u>R 4 W</u>
2. Distance and direction from nearest town or city: <u>1 E 1/2 No Cheney KS.</u>			3. Owner of well: <u>Don Harvey</u> R.R. or street: <u>6127 W. Central</u> City, state, zip code: <u>Wichita KS 67212</u>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>11</u> in. Completion date: <u>4/16/79</u> Well depth <u>65</u> ft.	
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
5. Type and color of material		From		To	
<u>Top soil</u>		<u>0</u>		<u>2</u>	
<u>Red clay</u>		<u>2</u>		<u>12</u>	
<u>fine sand</u>		<u>12</u>		<u>18</u>	
<u>red clay</u>		<u>18</u>		<u>25</u>	
<u>med. gravel</u>		<u>25</u>		<u>33</u>	
<u>brown shale</u>		<u>33</u>		<u>58</u>	
<u>blue-green shale</u>		<u>58</u>		<u>65</u>	
8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other					
9. Casing: Material <u>Galv</u> Height <u>Above</u> or below Threaded ☒ Welded ☒ Surface <u>12</u> in. RMP ☒ PVC ☐ Weight <u>1.50</u> lbs./ft. Dia. <u>5</u> in. to <u>65</u> ft. depth Wall Thickness: inches or Dia. <u>in.</u> to <u>ft.</u> depth gage No. <u>1200</u>					
10. Screen: Manufacturer's name <u>Sunflower</u> Type <u>200</u> Dia. <u>5 in</u> Slot/gauze <u>1/16</u> Length <u>30 ft</u> Set between <u>35</u> ft. and <u>65</u> ft. Gravel pack <u>yes</u> Size range of material <u>3/8</u>					
11. Static water level: <u>12</u> ft. below land surface Date <u>4/16/79</u>					
12. Pumping level below land surfaces: <u>20</u> ft. after <u>1/2</u> hrs. pumping <u>15</u> g.p.m. <u>ft.</u> after <u>hrs.</u> pumping <u>g.p.m.</u> Estimated maximum yield <u>20-30</u> g.p.m.					
13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>mo./day/yr.</u>					
14. Well head completion: <u>12</u> inches above grade					
15. Well grouted? <u>yes</u> With: <u>Neat cement</u> ☐ Bentonite ☒ Concrete ☐ Depth: From <u>2</u> ft. to <u>12</u> ft.					
16. Nearest source of possible contamination: <u>100</u> ft. Direction <u>E</u> Type <u>Septic</u> Well disinfected upon completion? ☒ Yes ☐ No					
17. Pump: ☒ Not installed Manufacturer's name <u>HP</u> Model number <u>HP</u> HP <u>Volts</u> Length of drop pipe <u>ft.</u> capacity <u>g.p.m.</u> Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other					
18. Elevation:					
19. Remarks: <u>Customer to furnish 4x4x4" slab around well at grade</u> <u>Per State Regulations</u> <u>Signed X Don Harvey</u>					
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Wm. R. H. 318</u> Business name <u>Sedgwick KS</u> License No. <u>4/16/79</u> Address <u>Wichita KS</u> Signed <u>Don Harvey</u> Date <u>4/16/79</u> Authorized representative					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5