


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Sedgwick</u>	Fraction <u>NW 1/4 NW 1/4 NW 1/4</u>	Section number <u>5</u>	Township number <u>T 28 S</u>	Range number <u>R 4 E</u>
2. Distance and direction from nearest town or city: <u>1/2 No Cheney KS.</u>		3. Owner of well: <u>Clarence Rau</u>		R.R. or street: <u>503 no Oakfield</u>		
Street address of well location if in city:		City, state, zip code: <u>Cheney KS 67025</u>				
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>11</u> in. Completion date <u>3/21/78</u>		
				Well depth <u>66</u> ft.		
5. Type and color of material		From		To		7. Cable tool ☒ Rotary ☐ Driven ☐ Dug
<u>Top Soil</u>		<u>0</u>		<u>4</u>		☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
<u>Red clay</u>		<u>4</u>		<u>13</u>		8. Use: ☒ Domestic ☐ Public supply ☐ Industry
<u>Red shale</u>		<u>13</u>		<u>18</u>		☐ Irrigation ☐ Air conditioning ☐ Stock
<u>Blue-green shale</u>		<u>18</u>		<u>21</u>		☐ Lawn ☐ Oil field water ☐ Other
<u>Red shale</u>		<u>21</u>		<u>50</u>		9. Casing: Material <u>PVC</u> Height <u>0</u> Above or below
<u>Blue-green shale</u>		<u>50</u>		<u>54</u>		Threaded ☐ Welded ☒ Surface <u>12</u> in.
<u>Red shale</u>		<u>54</u>		<u>66</u>		RMP <u>5</u> PVC ☒ Weight <u>2.56</u> lbs./ft.
						Dia <u>5</u> in. to <u>66</u> ft. depth Wall Thickness: inches <u>1.25</u>
						Dia. <u>5</u> in. to <u>66</u> ft. depth gage No. <u>258</u>
						10. Screen: Manufacturer's name <u>M.P.I.</u>
						Type <u>Sch 40</u> Dia. <u>5 in</u>
						Slot/auze <u>1/16</u> Length <u>30</u> ft.
						Set between <u>36</u> ft. and <u>60</u> ft.
						Gravel pack? <u>yes</u> Size range of material <u>3/8</u>
						11. Static water level: <u>22</u> ft. below land surface Date <u>3/21/78</u>
						12. Pumping level below land surfaces:
						<u>16</u> ft. after <u>15</u> hrs. pumping <u>15</u> g.p.m.
						<u>30</u> ft. after <u>15</u> hrs. pumping <u>30</u> g.p.m.
						Estimated maximum yield <u>30</u> g.p.m.
						13. Water sample submitted: <u>X</u> Yes <u>X</u> No Date <u>3/21/78</u>
						14. Well head completion: <u>12</u> inches above grade
						<u>12</u> Pitless adapter
						15. Well grouted? <u>yes</u>
						With: <u>Neat cement</u> <u>X</u> Bentonite <u>X</u> Concrete
						Depth: From <u>30</u> ft. to <u>13</u> ft.
						16. Nearest source of possible contamination: <u>none</u>
						ft. <u>none</u> Direction <u>none</u> Type <u>none</u>
						Well disinfected upon completion? <u>X</u> Yes <u> </u> No
						17. Pump: <u>X</u> Not installed
						Manufacturer's name <u> </u>
						Model number <u> </u> HP <u> </u> Volts <u> </u>
						Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m.
						Type: <u> </u> Submersible <u> </u> Turbine
						<u> </u> Jet <u> </u> Reciprocating
						<u> </u> Centrifugal <u> </u> Other
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: <u> </u> Hill <u> </u> Slope <u> </u> Upland <u> </u> Valley		<u>Customer to furnish 4x4x4 slab around casing at grade according to State Regulations</u>		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
				Business name <u>Wenger Dally</u> License No. <u>318</u>		
				Address <u> </u>		
				Signature <u>Clarence Rau</u> Date <u>3/21/78</u>		
				Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5