


Sent to DHC
1-29-79

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction SW 1/4 SW 1/4 NW 1/4	Section number 5	Township number T 28 S R 4	Range number 4
2. Distance and direction from nearest town or city: NW Edge of Cheney Street address of well location, if in city:				3. Owner of well: City of Cheney R.R. or street: Cheney, Kansas 67025 City, state, zip code:		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 1/16/79 Well depth 40 ft.		
		Well No. 8		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Sand		0	2	9. Casing: Material stl. Height: Above below Threaded ☐ Welded ☒ Surface 42 in. RMP ☐ PVC ☐ Weight 43.77 lbs./ft. Dia. 12 in. to 33 ft. depth Wall thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 330		
Gray clay		2	10	10. Screen: Manufacturer's name Mustang - Stainless Type Wire Wrap Dia. 12" Slot/gauze 60 Length 7' 40 Set between 33 ft. and 40 ft. Gravel pack yes Size range of material 1/8 x 1/2		
Sandy clay		10	25	11. Static water level: 17' 3" below land surface Date 1/12/79		
Sand & gravel 3/8" down - brown		25	30	12. Pumping level below land surfaces: 33.75 ft. after 6 hrs. pumping 92 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 100 g.p.m.		
Gray clay		30	32	13. Water sample submitted: ☐ Yes ☒ No Date ☐		
Sand & gravel - brown		32	39	14. Well head completion: ☐ Pitless adapter 42 inches above grade		
Red shale - hard		39	40	15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 20 ft.		
				16. Nearest source of possible contamination: ft. 1200 Direction South Type Home Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☐ Not installed Manufacturer's name Layne & Bowler Model number 88351 HP 7 1/2 Volts 460 Length of drop pipe 35 ft. capacity 100 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. 1-25-79 Address Wichita, Kansas Signed [Signature] Date 1-25-79 Authorized representative		
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☒ Slope ☒ Upland ☐ Valley						

28
-40
-5
SW/SW/NW
1/4 1/4 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Farm WWC-5