

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number  
 COUNTY: 094 STANTON : NE 1/4 NE 1/4 SW 1/4 : 35 : T 28 S : R 40 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 4 1/2 MILES EAST & 1/2 MILE SOUTH OF JOHNSON

2 WATER WELL OWNER: TRIPLE J FARMS  
 RR#, St. Address, Box #: 846 S. ROAD G Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : JOHNSON, KS 67855- Application Number: 8,537

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 613 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 314 ft. below land surface measured on mo/day/yr 03/15/97  
 Pump test data: Well water was 343 ft. after 4 hours pumping 1285 gpm  
 Estimated Yield 1285 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 613 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 613 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT  
 SCREEN PERFORATED INTERVALS: From 355 ft. to 375 ft., From 485 ft. to 515 ft.  
 From 390 ft. to 450 ft., From 560 ft. to 610 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 613 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? SOUTH How many feet? 125

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	02 SILT			
5	57	01 CLAY			
57	60	05 SAND			
60	80	01 CLAY 31 CALICHE			
80	90	04 SANDY CLAY			
90	100	09 COARSE SAND			
100	105	01 CLAY			
105	120	09 COARSE SAND			
120	145	09 COARSE SAND 04 SANDY CLAY			
145	198	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/14/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/25/97 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 094 STANTON	NE 1/4 NE 1/4 SW 1/4	35	T 28 S	R 40 W

2 WATER WELL OWNER:	TRIPLE J FARMS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	846 S. ROAD G	Application Number: 8,537
City, State, ZIP code :	JOHNSON, KS 67855-	

FROM	TO	LITHOLOGIC LOG
198	220	09 COARSE SAND 04 SANDY CLAY
220	240	09 COARSE SAND 01 CLAY
240	265	09 COARSE SAND 14 MED GRAVEL
265	270	01 CLAY
270	295	09 COARSE SAND 14 MED GRAVEL
295	315	01 CLAY
315	340	09 COARSE SAND 13 FINE GRAVEL 14 MED GRAVEL
340	360	09 COARSE SAND 13 FINE GRAVEL 14 MED GRAVEL
360	375	09 COARSE SAND 13 FINE GRAVEL 14 MED GRAVEL
375	387	01 CLAY
387	450	09 COARSE SAND 13 FINE GRAVEL 14 MED GRAVEL
450	460	01 CLAY 19 SHALE
460	485	19 SHALE
485	515	23 SANDSTONE
515	540	19 SHALE
540	565	19 SHALE 23 SANDSTONE
565	610	23 SANDSTONE
610	620	31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/14/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/25/97 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Orvin J. Reichmuth*