

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
 COUNTY: 094 STANTON : SW 1/4 SW 1/4 SE 1/4 : 19 : T 28 S : R 40 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 MILE NORTH & 1/2 MILE EAST OF JOHNSON

2 WATER WELL OWNER: MARTIN, BLAKE
 RR#, St. Address, Box # : P. O. BOX 920 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : WINTER, KS 67867- Application Number: 4,647

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 619 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 331 ft. below land surface measured on mo/day/yr 04/30/97
 Pump test data: Well water was 360 ft. after 4 hours pumping 1255 gpm
 Estimated Yield 1255 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 619 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 619 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 366 ft. to 406 ft., From 0 ft. to 0 ft.
 From 456 ft. to 616 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 619 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHEAST How many feet? 179

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	11	07 FINE SAND			
11	20	04 SANDY CLAY 05 SAND			
20	30	04 SANDY CLAY 31 CALICHE 05 SAND			
30	105	05 SAND 01 CLAY 11 GRAVEL			
105	111	01 CLAY			
111	170	05 SAND 13 FINE GRAVEL			
170	219	05 SAND 13 FINE GRAVEL 01 CLAY			
219	359	05 SAND 11 GRAVEL 20 LIMESTONE			
359	393	05 SAND 11 GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 03/15/97 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/01/97
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form #WC 5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 094 STANTON | SW 1/4 SW 1/4 SE 1/4 | 19 | T 28 S | R 40 W

2 WATER WELL OWNER: MARTIN, BLAKE

RR#, St. Address, Box # : P. O. BOX 920

Board of Agriculture, Division of Water Resources

City, State, ZIP code : WINTER, KS 67867-

Application Number: 4,647

FROM	TO	LITHOLOGIC LOG
393	402	01 CLAY 05 SAND 20 LIMESTONE
402	426	19 SHALE 20 LIMESTONE
426	458	19 SHALE 23 SANDSTONE
458	495	23 SANDSTONE 19 SHALE 20 LIMESTONE
495	517	23 SANDSTONE 31 CALICHE
517	524	01 CLAY 31 CALICHE
524	585	23 SANDSTONE 31 CALICHE
585	615	23 SANDSTONE 31 CALICHE 20 LIMESTONE
615	620	20 LIMESTONE 31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/15/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/01/97 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce J. Richmond