

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 094 STANTON SW 1/4 SW 1/4 NE 1/4 29 T 28 S R 40 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM JOHNSON; APPX 3/4 MILE NORTH & 1 3/4 MILES EAST

2 WATER WELL OWNER: CLEARWATER FARMS Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: PO BOX 402 Application Number: 7,885  
 City, State, ZIP code: JOHNSON, KS 67855-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

NW	NE
SW	SE

X

4 DEPTH OF COMPLETED WELL 644 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 342 ft. below land surface measured on mo/day/yr 07/19/04  
 Pump test data: Well water was 369 ft. after 4 hours pumping 1280 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 644 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 644 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 359 ft. to 639 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 644 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	13	07 FINE SAND 04 SANDY CLAY			
13	20	01 CLAY			
20	30	07 FINE SAND			
30	40	01 CLAY			
40	97	05 SAND 11 GRAVEL 01 CLAY			
97	108	01 CLAY 05 SAND			
108	123	05 SAND 01 CLAY			
123	133	01 CLAY			
133	150	05 SAND 13 FINE GRAVEL			

RECEIVED  
 SEP 20 2004  
 BUREAU OF WATER

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/14/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04 under the business name of HENKLE DRILLING & SUPPLY by (signature).

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:      Fraction      Section Number      Township Number      Range Number  
COUNTY: 094 STANTON      SW 1/4 SW 1/4 NE 1/4      29      T 28 S      R 40 W

2 WATER WELL OWNER:      CLEARWATER FARMS  
RR#, St. Address, Box # : PO BOX 402      Board of Agriculture, Division of Water Resources  
City, State, ZIP code : JOHNSON, KS 67855-      Application Number: 7,885

FROM	TO	LITHOLOGIC LOG
150	315	05 SAND 11 GRAVEL 28 ROCK
315	324	01 CLAY
324	396	05 SAND 11 GRAVEL 28 ROCK
396	404	01 CLAY
404	416	07 FINE SAND 01 CLAY
416	424	01 CLAY
424	433	07 FINE SAND
433	474	23 SANDSTONE 31 CALICHE
474	480	01 CLAY
480	511	23 SANDSTONE 31 CALICHE
511	519	01 CLAY
519	535	31 CALICHE 23 SANDSTONE
535	542	31 CALICHE 19 SHALE
542	555	31 CALICHE 23 SANDSTONE
555	560	20 LIMESTONE 31 CALICHE
560	580	31 CALICHE 23 SANDSTONE
580	602	31 CALICHE 23 SANDSTONE
602	615	23 SANDSTONE 31 CALICHE
615	616	20 LIMESTONE
616	639	31 CALICHE 23 SANDSTONE
639	645	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/14/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145      This Water Well Record was completed on (mo/day/yr) 08/31/04 under the business name of HENKLE DRILLING & SUPPLY      by (signature) *Bruce R. Kitchin*