

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 094 STANTON NE 1/4 NE 1/4 NW 1/4 28 T 28 S R 40 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM JOHNSON; APPX 3 MILES EAST & 1 MILE NORTH

2 WATER WELL OWNER: VENTURE LAND, INC.
 RR#, St. Address, Box #: 6190 N ROAD G Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JOHNSON, KS 67855- Application Number: 11320

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

X
NW NE
SW SE

4 DEPTH OF COMPLETED WELL 650 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 338 ft. below land surface measured on mo/day/yr 07/16/04
 Pump test data: Well water was 364 ft. after 4 hours pumping 1000 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 650 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 650 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 350 ft. to 430 ft., From 0 ft. to 0 ft.
 From 485 ft. to 645 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 650 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	45	01 CLAY 31 CALICHE 05 SAND			
45	55	07 FINE SAND 08 MEDIUM SAND			
55	75	01 CLAY 20 LIMESTONE			
75	91	05 SAND			
91	102	01 CLAY 05 SAND			
102	140	05 SAND 01 CLAY			
140	166	07 FINE SAND 08 MEDIUM SAND			
166	199	05 SAND 13 FINE GRAVEL			
199	220	01 CLAY 05 SAND			

RECEIVED
SEP 20 2004
BUREAU OF WATER

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/11/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) -

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 094 STANTON NE 1/4 NE 1/4 NW 1/4 28 T 28 S R 40 W

2 WATER WELL OWNER: VENTURE LAND, INC.
RR#, St. Address, Box # : 6190 N ROAD G Board of Agriculture, Division of Water Resources
City, State, ZIP code : JOHNSON, KS 67855- Application Number: 11320

FROM	TO	LITHOLOGIC LOG
220	231	07 FINE SAND
231	240	01 CLAY
240	254	01 CLAY 05 SAND
254	300	07 FINE SAND 08 MEDIUM SAND 01 CLAY
300	323	05 SAND 13 FINE GRAVEL 28 ROCK
323	337	01 CLAY 05 SAND
337	343	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
343	359	07 FINE SAND 08 MEDIUM SAND 01 CLAY
359	390	05 SAND 11 GRAVEL 28 ROCK
390	400	31 CALICHE 23 SANDSTONE
400	413	23 SANDSTONE
413	420	23 SANDSTONE 31 CALICHE
420	430	23 SANDSTONE
430	436	31 CALICHE 20 LIMESTONE
436	480	19 SHALE 20 LIMESTONE
480	500	19 SHALE 23 SANDSTONE
500	534	31 CALICHE 23 SANDSTONE 19 SHALE
534	550	23 SANDSTONE 31 CALICHE
550	600	31 CALICHE 23 SANDSTONE 20 LIMESTONE
600	606	31 CALICHE 20 LIMESTONE
606	621	31 CALICHE 23 SANDSTONE
621	645	31 CALICHE 20 LIMESTONE 19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/11/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichert*