

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 094 STANTON	SE 1/4 SE 1/4 SW 1/4	26	T 28 S	R 40 W

Distance and direction from nearest town or city street address of well if located within city?
FROM JOHNSON; 4 MILES EAST

2 WATER WELL OWNER: JOSSEBRAND FARMS
RR#, St. Address, Box #: 303 N. STANTON
City, State, ZIP code: JOHNSON, KS 67855-
Board of Agriculture, Division of Water Resources
Application Number: 23,241

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M	---		---	
i	W			E
l	---		---	
e				
		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 618 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 320 ft. below land surface measured on mo/day/yr 02/18/05
Pump test data: Well water was 362 ft. after 4 hours pumping 1575 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 618 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 618 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 356 ft. to 436 ft.,	From 545 ft. to 555 ft.
	From 484 ft. to 504 ft.,	From 563 ft. to 613 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 618 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	53	04 SANDY CLAY 31 CALICHE 07 FINE SAND			
53	73	05 SAND			
73	82	01 CLAY 20 LIMESTONE			
82	106	07 FINE SAND 08 MEDIUM SAND			
106	141	01 CLAY 05 SAND			
141	164	05 SAND			
164	192	01 CLAY			
192	267	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
267	288	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/16/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/30/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 094 STANTON	Fraction SE 1/4 SE 1/4 SW 1/4	Section Number 26	Township Number T 28 S	Range Number R 40 W
--------------------------------------------------	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: JOSSERAND FARMS
RR#, St. Address, Box # : 303 N. STANTON
City, State, ZIP code : JOHNSON, KS 67855-

Board of Agriculture, Division of Water Resources
Application Number: 23,241

FROM	TO	LITHOLOGIC LOG
288	300	01 CLAY
300	328	01 CLAY 05 SAND
328	340	05 SAND
340	353	01 CLAY 05 SAND
353	363	05 SAND
363	385	01 CLAY
385	436	05 SAND 11 GRAVEL 28 ROCK
436	440	31 CALICHE
440	484	19 SHALE 20 LIMESTONE
484	504	31 CALICHE 23 SANDSTONE
504	542	31 CALICHE 20 LIMESTONE
542	555	31 CALICHE 23 SANDSTONE
555	564	31 CALICHE
564	613	31 CALICHE 23 SANDSTONE
613	620	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/16/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/30/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Richman*